

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

10-18-10E

Company- WIXSON ET AL
Farm- Downing

No. 1

SEC. 10 T. 18 R. 10E
NE NW NW

Total Depth. 2940'

Comm. 12-15-55

Shot or Treated.


Contractor.

Issued. 3-17-56

Corr. 2-8-56

County Lyon

KANSAS



Elevation. 1150'

Production. DRY

CASING:

15 1/2"	30'
13"	316'
10"	1580'
8 1/4"	2246'

7"	2600'
5 1/2"	2917'

Figures indicate Bottom of Formations.

cellar	8
shale	20
gravel	45
shale	65
lime	70
shale	100
sandy shale	105
gas 100 -105	
shale	215
sand HFW	245
shale	285
lime	305
shale	460
lime	470
shale	530
lime	590
shale	595
lime	605
shale	654
lime	665
shale	695
lime	705
shale	725
lime	745
shale	755
lime	770
shale	780
lime broken	795
shale	865
lime	895
shale	900
lime	920
shale & shells	940
shale	965
sandy shale	990
shale	1070
lime	1075
lime & shale	1120
lime 2 BWPH 1120	1145
shale	1195
lime 3 BWPH 1195-1205	1225
shale	1230
lime	1245
shale	1249
lime	1290
shale	1295
lime	1315
shale	1322
lime	1440
shale	1460
lime	1468
shale	1482
lime	1500
shale	1510
lime	1547
shale	1552
lime	1600
shale	1620

lime	1625
shale 1/2 BWPH 1650	1705
lime	1725
shale	1730
lime	1755
shale & shells	1785
lime	1820
shale	1825
lime	1852
shale	1865
lime	1870
sandy shale	1880
shale	1945
lime	1950
shale	1955
lime	1970
sand 1 1/2 BWPH 1970-80	1982
shale	1995
lime	2010
shale	2025
lime	2030
lime broken	2065
shale	2100
shale & shells	2125
shale	2130
lime	2135
shale	2170
lime	2185
sandy shale	2230
lime	2340
2 BWPH 2285- 1 @	2310'
shale	2343
lime	2362
2 BWPH 2345-2360	
shale	2368
lime	2533
HFW 2390-2395'	
shale	2536
lime	2580
shale	2681
broken lime	2685
shale	2707
lime	2850

HFW 2715-2720'

sand	2915
lime	2940
Total Depth	

Tops: Scout	
Lansing	1195
Kansas City	1322
Base Kansas City	1600
Marmaton	1860
Mississippi	2230
Kinderhook	2580
Misner	2707
Hunton	2708
Viola	2803
Simpson	2838
Simpson Sand	2848
Arbuckle	2912