

WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY  
Wichita, Kansas


23-18-10E

Company - Huber, Anderson & Haworth  
Farm - Ball No. 1

SEC. 23 T. 18 R. 10E  
NW SW NW

Total Depth. 2985  
Comm. 8-26-49 Comp. 10-7-49  
Shot or Treated. 500 gals.  
Contractor. Pabco Drlg. Co.  
Issued. 11-5-49

County. Lyon



Elevation. 1242 Jnd  
1241 L.S.  
Production. D & A

CASING:

8" set @ 196'  
5" set @ 1681'

Figures Indicate Bottom of Formations.

Lime	25
Sand	35
Lime & shale	197
Shale & lime	265
Shale & shells	770
Lime & shale	1330
Lime	1460
Lime & shale	1575
Shale & lime	1715
Lime & shale	2042
Shale & lime	2282
Lime	2610
Shale & lime	2817
Lime	2875
Shale & lime	2910
Shale & sand	2925
Lime	2985

DST 1577-97, op. 1 hr. rec. 30' mud.  
1604-18, op. 1 hr. rec. 5' F.O. 85'  
heavy oil cut mud.  
1618-25, op. 1 hr. rec. 180' S.W. and S.S.O.  
2015-42, op. 1 hr. rec. 6' rotary mud. N.S.  
2400-10, op. 1 hr. rec. 300' S.W. rainbow  
S.O. BHP 710#  
2881-2910, op. 1 hr. rec. 2550' sulphur wtr.  
BHP 990#

Perf. 22 shots 1603-11, N.S.  
24 K." 1603 $\frac{1}{2}$ -11 $\frac{1}{2}$ . F.U. 550' fluid/1 hr.  
84 BW & 9 BO/12 hrs.

Total Depth

FORMATION TOPS

Lansing	1261
B. K.C.	1660
Miss.	2281
B. Miss. ls.	2636
Hunton	2765
Viola	2790
Simpson	2878
Arbuckle	2943