

20" 10"
15 1-2 8 1-4
12 1-2 6 5-8
5 3-16

FARM Ridenour

NO. 1 COUNTY

Lyon

COMPANY J. A. Abell et al

CONTRACTOR H. W. Redden

COMMENCED

COMPLETED June 21, 1926.

TOTAL DEPTH 2030'

SHOT

QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

J. A. Abell,

Wichita, Kansas.
FIGURES INDICATE BOTTOM OF FORMATIONS.

ELEVATION 1174 L&S
INITIAL PRODUCTION D. & A.

REMARKS

Formation	Depth	Formation	Depth
soil	3	lime white	1130
clay	8	shale gray	1135
sand stone	11	lime white	1170
shale green	15	shale gray	1175
shale light	95	lime white	1200
lime shells	110	shale blue	1225
shale blue	155	(Set 9 1/4" pipe at 1225')	
lime gray	160	shale blue	1228
shale brown	170	lime white	1233
shale gray	175	shale green	1238
lime shells	182	shale brown	1250
shale dark	210	shale gray	1255
shale gray	275	lime gray	1290
lime shells	280	shale blue	1300
shale gray	285	lime gray	1323
lime gray	295	sand brown	1333
shale gray	330	shale dark	1340
lime shells	370	lime white	1385
lime	385	shale light	1485
shale gray	395	shale gray	1530
water sand	400	lime gray	1545
(3 Bailers water 395-400')		shale dark	1575
shale gray	415	shale gray	1595
lime gray	425	shale dark	1600
shale gray	430	lime sandy	1610
lime gray	465	shale gray	1710
shale green	470	shale blue	1755
lime gray	480	(Set 6 5/8" pipe at 1755')	
shale gray	500	shale blue & black	1915
lime gray	520	(Set 5-3/16" pipe at 1900')	
shale gray	530	shale sandy	1925
lime gray	535	shale blue	1980
shale gray	580	shale dark	1985
lime gray	585	shale gray	2000
shale gray	630	shale blue	2010
lime white	660	shale black	2018
mud blue	665	Lime Mississippi	2030
shale black	670	Total Depth (HFW)	2030
lime dark	675		
shale light	685		
lime white	700		
shale light	725		
shale gray	855		
shale brown	865		
shale black	872		
(Run 10" pipe at 872')			
lime gray	880		
shale gray	890		
lime gray	895		
shale gray	965		
lime gray	985		
(400' water in hole 985')			
water sand	990		
lime white	1015		
shale black	1020		
lime white	1030		
shale gray	1035		
lime	1080		
shale gray	1110		