

19-18-15E
Plotted
R.S.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location SE SW NW

Sec. 19 T. 18 R. 15E.

Casing Record

10"
20" 8 1/2"
15" 65/8"
12" 53/16"
Total Depth 2118'

Farm- Jones
Company- York State Oil Co.
Contr.-
Comm.- 10/10/28

County - Osage.
No. 1
Comp.- 12/5/28.

APR 1 1930



Shot Quarts Between
Correspondence Regarding This Well Should Be Referred to

Figures Indicate Bottom of Formations.
Date Issued. 3/29/1930.

Initial Production Dry.

Elevation 1144 ft. Hamell
1050 m.c. comp.
1128.48

Formation	Depth	Formation	Depth
surface	10	lime	1020
lime	25	shale	1048
shale	65	sdylime	1060
lime	70	shale	1080
shale	98	lime	1197
lime	120	shale	1260
shale	194	lime	1270
shells	215	shale	1502
shale	260	sdylime	1521
lime	262	shale	1666
shells	285	lime	1965
lime	290	shale	1980
shale	295	lime	2028
lime	300	shale	2085
shale	370	shale	2090
sand	380	shale brown	2108
shale	490	lime	2118
sand	560		
shale	605	TD	2118
sand	643		
lime	665		
shale	670		
lime	730		
shale	740		
lime	750		
shale	765		
sdylime	775		
shale	790		
sand	795		
shale	802		
shells	824		
shale	830		
lime	900		
shale	910		
lime	935		
shale	945		
lime	1005		
shale	1015		

PLUGGING RECORD: Nov. 20, 1928
5 3/16" wood plug at 2095 ft. mud & rock to 2070
6 5/8" " " " 1900 " " " " 1860
8 1/2" " " " 1540 " " " " 1510
10" " " " 1200 " " " " 1155
12 1/2" " " " 802 " " " " 772
15 1/2" " " " 40 "

Filled with mud and rock to top

7 1/2' min
2027' over min

Bureau

Well
Kan.
Owr

On Jones farm, section 19, Twp 18, Range 15, County Osage,
Contractor Loy & Corey Address, Chanute, Kansas
K State Oil Company, Inc., Address Caney, Kansas.

19-18-15E

record all water, Oil and Gas and if possible colors of formations.

ch 1128 or
1144

Jones #1

SE SW NW

Elev. 1128 L.S.

FORMATION		Thick- ness	Total Depth	FORMATION		Thick ness	Total Depth
Soil	Brown	10	10	Slate	Dark	20	1430
Lime	White, hard	15	25	"	Light	35	1465
Slate	Grey	40	65	"	Dark	10	1475
Lime	"	5	70	"	Light	23	1498
Slate	"	28	98	"	Pink	4	1502
Lime	White, med.	22	120	"	Light	19	1521
Slate	Grey	10	130	"	Dark	49	1570
Lime	"	15	145	"	Light	60	1630
Slate, Shelly,	Grey	70	215	"	Dark	36	1666
Shale	Grey	35	250	Miss. Lime	Grey, med.	5	1671
Lime	"	12	262	"	Brown, med.	35	1706
Slate, Shelly	"	23	285	"	Light, med.	12	1718
Lime	"	5	290	"	Grey	42	1760
Slate	Black	5	295	"	Brown, hard	30	1790
Lime	Grey	5	300	"	Grey, med.	5	1795
Slate	"	70	370	"	Brown, med.	40	1835
Sand	" soft	10	380	"	Brown, med.	40	1835
Slate	"	110	490	"	Grey, soft	5	1840
Sand	" soft	70	560	"	Grey, med.	60	1900
Slate	"	35	595	"	White, "	55	1955
Sand	"	48	643	"	Grey, med.	10	1965
Lime	"	22	665	Slate	" soft	15	1980
Slate	Black	5	670	Lime	Dark, hard	28	2008
Lime	Grey, med	60	730	"	Brown, med.	20	2028
Slate	"	10	740	Slate	Grey, soft	62	2090
Lime	"	10	750	Shell,	" med.	1	2091
Slate	"	15	765	Slate	Brown, soft	17	2108
Lime, sandy	" soft	10	775	Lime	?, med.	11	2119 1/2
Slate	"	15	790				2119 1/2
Sand	"	5	795				7. D.
Slate, shelly	"	25	820				
Lime	" Hard	4	824				
Slate	"	6	830				
Lime	" med.	70	900				
Slate	"	10	910				
Lime	" med.	25	935				
Slate	"	10	945				
Lime G	" med	60	1005				
Slate	" soft	10	1015				
Lime	"	5	1020				
Slate	"	28	1048				
Slate, sandy	"	12	1060				
Slate	"	120	1180				
Lime	" hard	17	1197				
Slate	" soft	63	1260				
Lime	" med	10	1270				
Slate	Light	85	1355				
"	Sandy, Dk	35	1390				
"	Light	20	1410				

Abandonment record
filed at Lyndon, Kansas
Court house

Location
SW SE NW 19-18-15E

15 1/2 40'
12 1/2 575
10 802
8 1/4 1200
6 5/8 1680
5 3/8 2031
} all pulled

Herman Fisher Field Supt.
P.A. Mason Operator