

Company Walters & Ewbank

Farm Carl Ranney No. 1

Total Depth 720

Comm. 8/28/37

Shot or Treated

Contractor

Issued


Comp. 9/11/37

Sec. 36 T. 18 R. 22

Loc. $E\frac{1}{2}$ of NW corner

NW 1/4

County Miami



Casing

20 in.	10 in.
15 1-2	8 1-4
12 1-2	6 5-8 434
13 3-8	5 3-16

Elevation

Production

HFV

4 7/8 540
Figures Indicate Bottom of Formation

soil	1
shells	3
lime	16
shale	22 blue
lime	24
shale	44
lime	50
shale	92
lime	102
shale	114 blue
lime	145
shale	150 black water
lime	170
shale	174 black water
lime	176
shale	180 dark white
lime	186
shale	333
shale	343 white
shale	350 white sdy
lime	370
shale	372 light
lime	380
shale	402 light
shale	415 black - little gas

lime	420
shale	436 light grey
lime	439 top of lime
blk shale	445 gas & some water
shale	460
lime	482
shale	490 grey
lime	496 black - little gas &
lime	501 wtr.
shale	515 light
shale	521 blk-gas-lit. water
sand	540 water
shale	546 light
dk shale	560
shale sdy	570
dk shale	601
lime	603
blk shale	608 gas & wtr
l shale	635
shale	668 blk wtr
l shale	674
water sand	720 hole full