

**WELL LOG**  
**Dan Hankinson**  
**October 16 – October 17, 2002**

<u>Thickness of Strata</u>	<u>Formation</u>	<u>Total</u>
10	soil & clay	10
2	limestone	12
13	shale	25
5	limestone	30
1	shale	31
16	limestone	47
12	shale	59
5	limestone	64
2	shale	66
13	limestone	79
4	shale	83
5	limestone	88
3	shale	91
19	limestone	110
10	shale	120
10	sandstone	130- GAS
20	shale	150

**10-16-02**

**6 PM**

**Drilled an 12 1/4" hole to 20.4' and set 20.4' of 8 5/8" surface casing and cemented with 8 sacks Portland cement.**

**10-17-02**

**5 PM**

**Drilled a 7 5/8" hole to 150' and set 119' of used drifted and tested 4 1/2" casing with a cement basket at 119'. Then cemented with 35 sacks cement.**

**10-18-02**

**Ran line to the house, assembled fittings, tank, etc.**