

Company Interstate Pipe Line Co.

Farm J. W. White

No. 1

Total Depth 1005'

Comm.

Shot or Treated

Contractor

Issued

Comp.

Sec. 16

T. 18s


R. 25E

Loc.

SWC NE NE

County

MIAMI



Elevation

Production

Casing

20 in.	10 in.
15 1-2	8 1-4
12 1-2	6 5-8
13 3-8	5 3-16

Figures Indicate Bottom of Formation

Soil & Clay	8'	Lime	495
Lime	15	Light Shale	498
Clay	28	Black Shale	505
Shale	39	Gray Sandy Shale	520 -
Lime	41	Black Shale	525
Blue Shale	94	Blue Shale	585
Gray Lime	102	Sandy Dark Shale	610
Shale	115	Light Sandy Shale	630
Gray Lime	151	Red Rock	637
Shale & Lime	156	Sandy Shale	650
Lime	180	Dark Sandy Shale	675
Shale	182	Dark Shale & Slate	695
Lime	185	Oil sand	717 1/2
Shale & Black Slate	190	Dark hard shale	740
Lime	195	Black Slate	745
Black Shale	200	Dark Sandy Shale	755
Blue Shale	214	Sand	765
Gas Sand	230	Sandy Shale	775
Blue Shale	300	Sand	780
Bart Sand & Shale	305	Sandy Shale	790
Green Shale	335	Black Sandy Shale	800
Dark Shale	347	Dark Sandy Shale	805
Sandy Lime	354	Brown sand	810
Blue Shale	370	Gray Sandy Shale	815
Sand & Shale	382 gas show	Gray Sand	825
Blue Shale	395	Black Sandy Shale	845
Sandy Lime	400	White Shale	860
Sand & Dark Shale	420	Gray Sand	867
Grey Brown Lime	429	Sandy Lime	870
Blue Shale	434	Lime & Blue Flint	890
Dark Shale	448	Sandy Shale	895
Sand	453 gas show.	Sandy Lime & Blue Flint	900
Sandy Shale	465	Sandy Lime	905
Sandy Lime	469	Lime & Sand	940
Black Shale	470	Lime & Blue Flint	999
Sandy Lime	483	Black Slate	1000
Sandy Shale	488	Sand	1005 Sulphur and salt water.