

1-19-4E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STEVE YOUNG
Farm- Wight No. 2

SEC. 1 T. 19 R.4E
NE NW SE

Total Depth. 2359'
Comm. 5-30-58 Comp. 6-2-58
Shot or Treated.
Contractor. Sunflower Drlg. Co.
Issued. 7-16-60

County Marion
KANSAS



CASING:

8 5/8" 200' w/200 sx cem.
4 1/2" 2337' w/50 sx cem.

Elevation. 1445' G.L.

Production. 10 BOPD

Figures indicate Bottom of Formations.

soil	5
clay, shale	45
red bed	50
lime, shale	290
lime	375
shale, shells	1315
lime, shale	1575
shale, shells	1795
lime, Kansas City	2136
shale, shells	2332
chat, Mississippi	2344 RTD
chat	2359
Total Depth	

TOPS: SCOUT
Mississippi 2332

sft char, oil show 2343-2348
150' fluid in hole
chat harder no inc. in fluid 2348-2350
chat sft, blue & sdy, Inc. in oil & wtr.
Well fracked 5-29, 1350 BW & 10,000 sand.

Plenty gas, wtr fillup 1700'