


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SATURN OIL & GAS CO., INC.
Farm. Swigert No. 1

SEC. 31 T. 19 R. 10E
NE NE SE

Total Depth. 2925
Comm. 5-10-56 Comp. 5-18-56
Shot or Treated.
Contractor. White & Ellis Drilling, Inc.
Issued. 9-1-56

County Lyon KANSAS



CASING:
8 in. 105'

Elevation. 1240 KB

Production. Dry

Figures indicate Bottom of Formations

soil	1	Mississippi	2314
lime	2	Kinderhook	2601
clay	6	Misener	2719
lime	15	Hunton	2722
shale	65	Viola	2775
lime	79	Simpson	2812
shale	87	Arbuckle	2875
lime	118		
shale & shells	575		
lime	610		
shale & shells	650		
lime	708		
shale & shells	872		
lime	876		
shale & shells	933		
lime	962		
shale & shells	975		
shale & lime streaks	1040		
sandy shale	1080		
gray shale & shells	1288		
lime	1644		
shale & shells	1655		
lime	1675		
shale	1678		
lime & shale streaks	1701		
shale & shells	1801		
shale & lime, sandy	1825		
white lime	1878		
lime w/ shale streaks	1950		
shale & shells	1984		
sandy shale & shells	2028		
shale & lime streaks	2088		
black shale	2090		
lime & shale streaks	2118		
shale & lime streaks	2262		
lime w/ shale streaks	2304		
brown lime & shale streaks	2314		
lime, hard streaks	2375		
lime w/ chatty streaks	2390		
hard brown lime	2417		
chatty lime	2420		
chert	2446		
chatty lime, not rough	2517		
lime w/ hard streaks	2601		
shale	2719		
Hunton	2739		
lime	2775		
Simpson sand	2812		
Arbuckle lime	2925		
Total Depth			
Tops:			
Lansing	1288		
Kansas City	1400		
Base KC	1701		
Marmaton	1726		
Cherokee	1970		