



694356

Date	Depth	
8/5 D.S.T. #1	2005-55	- Op 1 hr., wk. bl. fo
		40", Rec. 30' mud, SI 30"
		BHP 785-700#, FP 26-42#
8/6	2100	Drig.
8/7	2220	Miss. (-789)
D.S.T. #2	2222-2245'	- Op 1 1/4 hrs., GTS
		in 6 1/2", Ga. 105 Mcf - 15"
		98 Mcf - 25" (stal
		Rec. 65' mud in D.C., SIP(30"
		828-802#, FP 60-32#
D.S.T. #3	2245-70'	- Op 1 hr., GTS in 7",
		Ga. 98,000 - 12"
		98,000 - 25"
		105,000 - 40"
		106,000 - 60"
		SIP (30") 828-785#, FP 42-50#
		Rec. 70' mud in D.C.
8/8	2305'	R.T.D. - 4 1/2" @ 2305' w/50 sx
		8/8/62
		12% salt, P.D. @ 2:00 a.m.
8/16	M.I.C.T.	(Ran log), Perf. 2230-50'
		w/4 <sup>s</sup> ft., Frac. 15,500# sd-wtr.,
		Flowing at rate of 3,500 Mcfg
8/30	D.S. Gas Co. esti.	- 6,000,000 cfg/d
8/30	C.S. Gas Co. 4-pot:	4,800,000 cfg/d
11/6	S.C.C. test:	-1,423,000' cfg/d