

11-19-2E


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Riesen No. 1

SEC. 11 T. 19 R. 2E
NE NE NE

Total Depth. 2908
Comm. 11-4-53 Comp. 11-13-53
Shot or Treated.
Contractor. Birmingham-Bartlett Drilling Co.
Issued. 1-16-54

County Marion
KANSAS



Elevation. 1380

Production. Dry

Figures indicate Bottom of Formations.

surface clay, shale & shells	150
lime & shale	900
shale & shells	1485
lime & shale	1950
lime	2310
lime & shale	2503
lime	2540
cherty lime	2602
lime	2650
lime & shale	2805
shale	2905
lime	2908 RTD
Total Depth	

plastic to 2907. Perf. 2903-07 with 28 jet charges. S.O. and water. Acidized with 250 gal. broke at 1400#. Swab. load and swb. 1 1/8 BFPH for 8 hrs. 70% water, 30% oil Re-acidized with 1000 gals. max. 200#, min. 100# in 26 min. Swb. load & Swb. 10 BO plus 197 BW in 10 hrs. Swb. 4 Bo, 76 BW in 4 hrs. Temp. aban. - to hold for SWDW.

Tops:	
Heebner	1716
Lansing	1929
Mississippi	2497
Kinderhook	2664
Misener	2903
Viola	2905

DST: #1 2478-2510' open 60 min. weak diminishing blow, rec. 12' mud, BHP 35#.
DST: #2 2898-2907' open 90 min., moderate blow, rec. 50' oil & 15' mud BHP 885#.

R.T.D. 2907

DP and deepened 2' to 2909, bailed 5 GO & 10 GWP for 5 hrs. Acidized with 250 gal. Pressured up to 200# then went on vacuum. Swabbed load and swabbed 12 BO plus 252 BW in 17 hrs. Swb. 2 BO plus 79 BW in 5 hrs. Plugged back with plastic to 2902. Drilled