


32-19s-3E



DRILL STEM TEST REPORT

Prepared For: **American Energies Corp**

155 N Main Ste 710
Wichita KS 67202

ATTN: Doug Davis

32 19S3E Marion KS

Unruh#2-32

Start Date: 2006.05.26 @ 09:47:20

End Date: 2006.05.26 @ 16:49:35

Job Ticket #: 24099

DST #: 1


15-115-21349-00-00

RECEIVED
JUN 26 2006
KCC WICHITA

Trilobite Testing, Inc

PO Box 362 Hays, KS 67601

ph: 785-625-4778 fax: 785-625-5620



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

American Energies Corp

155 N Main Ste 710
Wichita KS 67202

ATTN: Doug Davis

Unruh#2-32

32 19S3E Marion KS

Job Ticket: 24099

DST#: 1

Test Start: 2006.05.26 @ 09:47:20

GENERAL INFORMATION:

Formation: Miss.

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 11:47:35

Time Test Ended: 16:49:35

Test Type: Conventional Bottom Hole

Tester: Gary Pevoteaux

Unit No: 23

Interval: 2494.00 ft (KB) To 2510.00 ft (KB) (TVD)

Total Depth: 2510.00 ft (KB) (TVD)

Hole Diameter: 7.88 inches Hole Condition: Poor

Reference Elevations: 1381.00 ft (KB)

1373.00 ft (CF)

KB to GR/CF: 8.00 ft

Serial #: 6771

Inside

Press@RunDepth: 134.65 psig @ 2495.00 ft (KB)

Start Date: 2006.05.26

End Date:

2006.05.26

Start Time: 09:47:25

End Time:

16:49:34


Capacity: 7000.00 psig

Last Calib.: 2006.05.26

Time On Btm: 2006.05.26 @ 11:47:20

Time Off Btm: 2006.05.26 @ 14:52:34

TEST COMMENT: IF Fair blow Steady increase to 13 in
ISI No blow
FF Fair blow Steady increase to 10 in
FSI No blow



PRESSURE SUMMARY


Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	1242.56	97.22	Initial Hydro-static
1	17.39	96.87	Open To Flow (1)
33	104.56	99.62	Shut-In(1)
90	566.45	99.58	End Shut-In(1)
91	106.89	99.45	Open To Flow (2)
121	134.65	100.44	Shut-In(2)
185	557.55	100.73	End Shut-In(2)
186	1173.65	101.19	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
186.00	SW Rw .05 OHMS @ 92 deg	0.91
80.00	MW 37%M 63%W	1.12

Gas Rates

	Choke (Inches)	Pressure (psig)	Gas Rate (Mcf/d)
--	----------------	-----------------	------------------



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

TOOL DIAGRAM

American Energies Corp

Unruh#2-32

155 N Main Ste 710
Wichita KS 67202

32 19S3E Marion KS

Job Ticket: 24099

DST#: 1

ATTN: Doug Davis

Test Start: 2006.05.26 @ 09:47:20

Tool Information


Drill Pipe:	Length: 2316.00 ft	Diameter: 3.80 inches	Volume: 32.49 bbl	Tool Weight: 2100.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer: 30000.00 lb
Drill Collar:	Length: 186.00 ft	Diameter: 2.25 inches	Volume: 0.91 bbl	Weight to Pull Loose: 61000.00 lb
		Total Volume:	33.40 bbl	Tool Chased 0.00 ft
Drill Pipe Above KB:	35.00 ft			String Weight: Initial 54000.00 lb
Depth to Top Packer:	2494.00 ft			Final 54000.00 lb
Depth to Bottom Packer:	ft			
Interval between Packers:	16.00 ft			
Tool Length:	43.00 ft			
Number of Packers:	2	Diameter: 6.75 inches		

Tool Comments:

Tool Description

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			2468.00	
Shut In Tool	5.00			2473.00	
Hydraulic tool	5.00			2478.00	
Jars	5.00			2483.00	
Safety Joint	2.00			2485.00	
Packer	4.00			2489.00	27.00 Bottom Of Top Packer
Packer	5.00			2494.00	
Stubb	1.00			2495.00	
Recorder	0.00	6771	Inside	2495.00	
Perforations	10.00			2505.00	
Recorder	0.00	13222	Outside	2505.00	
Bullnose	5.00			2510.00	16.00 Bottom Packers & Anchor

Total Tool Length: 43.00



TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

FLUID SUMMARY

American Energies Corp

Unruh#2-32

155 N Main Ste 710
Wichita KS 67202

32 19S3E Marion KS

Job Ticket: 24099

DST#: 1

ATTN: Doug Davis

Test Start: 2006.05.26 @ 09:47:20

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

126000 ppm

Viscosity: 43.00 sec/qt

Cushion Volume:

bbl

Water Loss: 9.99 in³

Gas Cushion Type:

Resistivity: 0.00 ohm.m

Gas Cushion Pressure:

psig

Salinity: 1500.00 ppm

Filter Cake: 0.20 inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
186.00	SW Rw .05 OHMS @ 92 deg	0.915
80.00	MW 37%M 63%W	1.122

Total Length: 266.00 ft

Total Volume: 2.037 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #: none

Laboratory Name:

Laboratory Location:

Recovery Comments:

Serial #: 6771

Inside

American Energies Corp

32 19S3E Marion KS

DST Test Number: 1

