

4-19-4E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company. SLUSSER DRILLING CO.  
Farm. Lou Holub No. 3

SEC. 4 T. 19 R. 4E  
SW SW NW

Total Depth. 2453'  
Comm. 12-28-60 Comp. 1-21-61  
Shot or Treated.  
Contractor. Slusser Drlg. Co.  
Issued. 4-1-61

County Marion



Elevation. 1419' RB

Production. Dry

Figures indicate Bottom of Formations.

CASING:	
8 5/8"	160'
5 1/2"	2380'
surface soil	5
shale & lime	80
broken lime	130
lime	200
lime & shale	630
shale & shells	975
shale & lime	1800
lime	2150
lime & shale	2275
shale	2374
chat	2380 RTD
chat show of gas	2389
chat	2404
chat soft	2413 slight show of oil & little water
chat	2420
chat soft	2428 increase in water
chat	2437
chat & shale	2445
chat, lime & red rock	2453 CTTD
Total Depth	
TOPS: SCOUT	
Kansas City	1800
Mississippi	2374