

KANSAS

State Geological Survey

WELL COMPLETION REPORT AND DRILLER'S LOG WICHITA, BRANCH

S. 16 T. 19S R. 5 E
2055 FEL 1320 FNL

API No. 15 — 115 — 20717
County Number

Operator
DAMSON OIL CORPORATION

Address
BOX 4391, Houston, Texas 77210

Well No. 2 Lease Name
W. R. Carpenter

Footage Location
1320 feet from (N) (S) line 2055 feet from (E) (W) line


Principal Contractor Geologist
INLAND DRILLING CO.

Spud Date Date Completed Total Depth P.B.T.D.
1-26-81 1-31-81 2300 2258

Directional Deviation Oil and/or Gas Purchaser
Cities Service

County Marion

640 Acres
N



Locate well correctly

Elev.: Gr. 1412

DF KB1417

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
PRODUCTION	6 1/4	4 1/2	10.50#	2298	50:50 POZ	150	10% Salt 0.75% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			One	Jet	2182-2232

TUBING RECORD

Size	Setting depth	Packer set at
2-3/8 EUE	2140	--

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
90 Barrels 3% gelled HCL	2182-2232

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
	Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil bbls. 0 Gas MCF 0 Water bbls. 0 Gas-oil ratio CFPB 0
Disposition of gas (vented, used on lease or sold)	Producing interval (s)
VENTED - WILL POTENTIAL AFTER HOOK-UP	2182-2232

Operator
DAMSON OIL CORPORATION

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

2

Lease Name

W. R. Carpenter

GAS

S 16 T 19S R 5 ^W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
TOP SOIL	0	5		
LIME	5	20		
CLAY	20	27		
LIME	27	40		
CLAY AND SHALE	40	55		
SHALE	55	70		
LIME	70	85		
LIME AND SHALE	85	1740		
LIME	1740	2182		
MISS. CHAT	2182	2300		
			MISS. CHAT CN & CD Ran	2182-2300

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature

Title

Date

228375