


Company- SLUSSER DRIG. CO. ET AL
Farm- Meirhoff No. 1SEC. 27 T. 19 R. 5E
SE NE SWTotal Depth. 2439
Comm. 12-20-51
Shot or Treated.
Contractor.
Issued. 1-19-52

Comp. 1-6-52

County Marion
KANSASCASING:
No casing recordElevation. 11471 R.B.
1741 (m)

Production. Dry

Figures Indicate Bottom of Formations.

no log above 1500'		shale, drk green, maroon	
shale gry	1516	& drk gry	2112
lime gry xylm	1522	lime lgt dense xylm	
shale gry	1560	partly oolitic	2122
sand lgt fine micaceous	1567	sand, green-gry fine	2135
shale gry sandy	1572	lime green lithographic	
sand lgt fine micaceous	1578		2164
shale gry	1644	shale, drk with plant	
lime gry dense xylm	1648	remains	2171
shale gry	1655	lime gry dense	2176
lime gry dense xylm	1658	shale, green gry	
shale gry	1710	pyritic	2183
lime buff to gry oolitic	1717	lime gry dense	2192
shale gry limey	1723	shale blk	2194
shale drk	1726	lime lgt dense xylm	2206
lime lgt dense xylm	1738	shale blk	2208
shale gry	1744	chert lgt tripolitic	
lime, lgt dense xylm	1754	w/green & maroon shale	
shale gry	1758	laminations	2225
lime, lgt to gry dense		chert wht solid	2236
xylm slightly cherty	1784	shale maroon	2238
shale gry green & maroon	1787	lime, lgt dense xylm	2242
lime buff dense xylm		shale gry	2283
oolitic	1792	shale gry limey	2290
shale gry	1802	shale gry	2316
lime gry dense xylm	1814	lime buff xylm	2323
lime lgt oolitic leached		shale gry	2345
porous	1821	shale brown-gry to drk	
lime drk gry dense xylm		spores	2402
partly cherty	1846	shale green-gry to green	
lime lgt xylm oolitic		with thin dolomitic	
porous	1855	lime stringers	2419
lime lgt dense xylm	1874	lime wht dense xylm	
lime gry dense xylm	1907	slightly cherty	2439
shale gry	1912	Total Depth	
lime gry dense xylm	1926		
lime lgt to buff xylm		Tops:	
oolitic leached porous	1931	Brown Lansing	1710
lime buff very dense	1935	Lansing White	1726
lime wht dense xylm partly		Base-Kansas City	2058
leached	1942	Miss.	2208
lime gry dense xylm	1962	Kinderhook	2242
shale gry	1964	Chattanooga	2345
lime drk gry dense xylm	1976	Maquoketa	2402
lime lgt xylm oolitic	1980	Viola	2419
lime lgt dense xylm partly			
cherty	2004	All depths in log are	
lime gry dense xylm		from rotary bushing.	
cherty	2018		
shale green & maroon	2023	Total Depth 2439 in Viola	
lime gry dense xylm	2026		
shale blk	2030	No show of oil observed.	
lime, lgt to gry dense			
finely xylm	2058		
shale gry pyritic	2076		
sand gry micaceous silty	2094		
lime gry to drk dense			
xylm	2100		
lime buff very dense	2104		