

KANSAS DRILLERS LOG

S. 29 T. 19 R. 5 E

API No. 15 — 115 — 20,300
County Number

Loc. 660' FEL & 1980' FSL

Operator
R. L. Burns Corp.

County Marion


Address
Well No. #1 Lease Name Stroda

Footage Location 1980 660
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Kan Go, Inc. Geologist Frank S. Mize

Spud Date 11-11-76 Total Depth 2365 P.B.T.D. 2358

Date Completed Oil Purchaser Summit



Elev.: Gr. 1476
DF KB 1486

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface pipe	12 1/4	8 5/8	28	197'	Class A	150	cementers error 3% gel
production pipe	7 7/8	4 1/2	9 1/2	2362'	Class A	150	3% cacl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	3 1/8 D.P.	2268-80
TUBING RECORD			1	3 1/8 D.P.	2286-96
Size	Setting depth	Packer set at	1	3 1/8 D.P.	2303-10

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
30,000 gal. mitrofiad gelled frac fluid; 30,000 # 20-40 sand;	Intervals perfed
30,000 # 10-20 sand; flush with 21,000 scf N ₂	

INITIAL PRODUCTION

Date of first production 1-28-77	Producing method (flowing, pumping, gas lift, etc.) flowing				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	500 MCF	40 bbls.		CFPB
Disposition of gas (vented, used on lease or sold) sold			Producing interval (s) Mississippi Chat		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

R. L. Burns

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

1

Lease Name

Stroda

S 29 T 19 R 5 E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Frank A. [Signature]
Signature

GEOLOGIST
Title

3-22-22
Date

15-115-20300

State Geological Survey
WICHITA, KANSAS

29-19-5E

STATE	KANSAS	11-3-73	MAP NO.	S-T-R	29-19S-5E	D
OPER	R. L. BURNS CORP			SPOT	C NE SE	INIT
	BOX 277, MARION, KS			CO	MARION	SUS
WELL	1 STRODA			ELEV	1430 TS	FIN
CONTR	KAN-GO				K.B. 1986	
FIELD	LOST SPRINGS(KC-MISS)				G.L. 1976	
IP	OPERATIONS SUSPENDED				TOPS NOT AVAIL	
	API 15-115-20300				RTD EST 2500-1070	
	SPUD 10-30-76 , 11-11-76				TD IN MISS KH 2365-897	
	RTD EST 2500, Pipe Set					
	OPERATIONS SUSPENDED 10-26-76					

COMP ISSUED 11-15-76



LOG	TOPS	GEO. - FRANK MIZE	
L	1764	-378	CORED FROM 2256-2316 REC. 58 1/2' GSG, SSO. RAN IEL, SWN, CD. PERFS 2268-80/12, 2286-96/10, 2303-10/17. FRAC w/ 30,000 GAL NITROFIED GEL FRAC FLUID & 60,000# SAND. FLUSH w/ 21,000 scf N ₂ .
Mch	2264	-778	
Mlm	2311	-893	
KH	2390	-872	
RTD	2365	-897	
TD IN KH			
PBTD	2358		