

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-115-20415

S. 30 T. 19S R. 5E
Loc. C SW/4 NE/4
County Marion
640 Acres

API No. 15 — 115 — 20415
County Number

Operator
George A. Reed

Address
645 Fourth Financial Center Wichita, Kansas 67202


Well No. # | Lease Name
| Nienstedt

Footage Location
1980 feet from (N) ~~XX~~ line 1980 feet from (E) ~~XX~~ line

Principal Contractor Geologist
Berentz Drilling Co. M. W. Smith

Spud Date Total Depth P.B.T.D.
April 26, 1978 2310

Date Completed Oil Purchaser
April 29, 1978



Locate well correctly
Elev.: Gr. 1434
DF 1437 KB 1439

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8-5/8	20#	162'	Reg. Port	175	3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator	George A. Reed	DESIGNATE TYPE OF COMP.: OIL, G. DRY HOLE, SWDW, ETC.: Dry Hole
Well No.	#1	Lease Name Nienstedt
S 30 T 19S R 5E E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SOIL	0	3	LANSING	
LIME & SHALE	3	520	LIMESTONE	1747 (-308)
SHALE & LIME	520	1750	BURGESS	
LIME LANSING KC	1750	2170	SANDSTONE	
SHALE	2170	2255	ZONE	2193 (-754)
LIME & CHAT MISS.	2255	2310	MISS. CHERT	2259 (-820)
TD	2310		GILMORE CITY	
			LIMESTONE	2295 (-856)
			TD	2310 (-1)
DST #1 2262-2275 (30-30-30-60) no water. IFP 17-17#; ISIP 258#;				Good blow. No gas. Recovered 15' mud. FFP 17-17#; FSIP 335 #
DST #2 2275-2310 (30-30-30-30) mud, no water. IFP 8-17#;				Weak to good blow. No gas. Recovered 15' ISIP 103#; FFP 17-17#; FSIP 86#

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p align="center"><i>Cindy Galloway</i> Signature</p> <p align="center">Cindy Galloway, Office Manger</p> <p align="center">Title</p> <p align="center">May 9, 1978</p> <p align="center">Date</p>
---------------	--

30-19-5E

LOG OF WELL

OPERATOR George A. Reed

Neinstadt #1

SW NE

CONTRACTOR Berentz Drilling Co.

Section 30-19-5e

Marion County, Ks.

Commenced w/Rotary 4-26-78

Elv KB

Completed w/Rotary 4-30-78

Casing: 8 5/8" 162' Cemented
w/175 sx

DST # 1

2262 - 2275

Rec. 5' Mud

Soil	3
Lime & Shale	520
Shale & Lime	1750
Lime Lansing - KC	2170
Shale	2255
Lime & Chat Miss.	2310 RTD

MAY 10 1978

CONSERVATION DIVISION
Wichita, Kansas