



| Date      | Depth                 | DLIO (Time 694314)  |
|-----------|-----------------------|---|
| 7/22      | 2222                  | Miss. Chat (-799)   |
| D.S.T. #1 | - 2224-45'            | - Op 1 hr., GTS in 2"<br>Ga. 537,000 - 15"<br>627,000 - 20"<br>648,000 - 25"<br>(stab. for 1 hr.) 686,000 - 30" |
|           |                       | Rec. 120' gas-cut mud & 60'<br>sli gas-cut salt wtr. in D.C.<br>BHP 825-779#, FP 135-141#                       |
| D.S.T. #2 | - 2245-95'            | - Op 40", GTS in 1",<br>Ga. 1,630 Mcf - 15" & stab  |
|           |                       | SI 30", Rec. 190' gas-cut mud<br>BHP 822-797#, FP 350-270#  |
|           | 2313                  | Miss. Lime (-890)   |
|           | 2330                  | R.T.D.  |
|           |                       | 4 $\frac{1}{2}$ " @ 2326' w/50 sx. cem.,<br>15% salt, P.D. @ 4:25 a.m. 7/23                                     |
| 7/30      |                       | M.I.C.T. (Ran Welex Log)<br>Perf. 2240-60' w/4 <sup>s</sup> ft.,<br>Frac. 25,000 sand                           |
| 7/31      |                       | Flowing at rate of 2,400 Mcf<br>650# csg. (esti. 12-15 mil of   |
| 8/1       |                       | Flowing at rate of 1,400 Mcf<br>680# csg., $\frac{1}{2}$ BFPH   |
| 8/6       | C.S. Gas Co. calc. of | have rec. 250' bbls. of 800 bbl<br>load   |
| 8/21      |                       | First Gas Run   |