

State Kansas County Marion

Company Messman-Rinehart Oil Co. Well No. 1

Farm Heise-Lehmann-Stenzel Unit

Survey 1

Block No. 02 Sec. 05 Twp. 19 S - Range 5 E

Co-Ord. Elev. 1429 D/F
1427 Gr

SW NW NE M-R Rig

Lehmann		
	Heise	
Stenzel		

32.8125%-A.A.Seeligson, Jr.
10.9375%-A.A.Seeligson, Sr.
21.875% -Chicago Group
21.875%- M-R Oil Co.
*12.5% -Lalicker & Scott
*-subj. to Agreement w/L&S
dated 1/7/60

2300' Miss. test

NOTE: Show Sketch of Lease and Well Location in Above Space

990

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

2310

Ft. from E. Line

Date	Depth	
7/5/62		Location Staked
7/8		Spud - 8-5/8" @ 190' w/120 sx.cem., 2 gel., 3 c.c. P.D. @ 9:00 p.m. 7/9/62
7/11	650	Drig.
7/12	1520	On bottom - #3 bit
7/13	2000	Drig.
7/14	2230	Miss. Chat (-799)
D.S.T. #1 - 2233-55 - Op 1 hr., GTS in 24"		(tstm)

Date	Depth	694335
	3530	Rec. 15' mud, BHP 805-800#,
	5000	FP 28-40#, Temp. 88°
D.S.T. #2	2255-2305'	- Op 1 hr., GTS in 3'
		Ga. 277,000 - 10"
		258,000 - 15"
		290,000 - 30"
		300,000 - 45"
		325,000 - 60"
		Temp. 96°
		BHP 683-845#, FP 85-138#,
	2305'	Miss. Lime
	2335'	R.T.D. - 4 $\frac{1}{2}$ " @ 2335' w/50 sx.
		15% salt, P.D. @ 9:30a.m. 7/15
7/28		M.I.C.T. (Ran Welex Log)
		Perf. 2254-69' w/4 ^S ft.
		Frac. 25,000 sd.
7/31		Flowing at rate of 1,600 Mcf,
		650# csg. (esti. 9-10 mil of)
8/1		Flowing at rate of 1,200 Mcf,
		700# csg., plus 1 BFPH
		200 bbl. rec. of 800-bbl. load
		SI for C.S. Gas Co. test
8/6	C.S. Gas. Co. calc. of	- 9,175,000 cf,
8/21		First gas run