

24-19-7E

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company • AMERADA PETRO. CORP.
Farm • Jensen No. 1


SEC. 24 T. 19 R. 7E
NE NE NE

Total Depth. 2165'
Comm. 3-8-49
Shot or Treated.
Contractor.
Issued. 6-11-49

Comp. 3-17-49

County. Chase

KANSAS



Elevation. 1193 Ind
(1192, C.S.)

Production. Dry & Abandoned

CASING:
8-5/8" 121'

Figures Indicate Bottom of Formations.

log starts	140
sand & shale	210
shale	230
sand	240
shale	320
lime & shale	390
shale	460
sand	480
shale	525
lime	535
shale	550
sand	560
shale	588
lime	630
sand	648
shale	677
lime	705
sand	742
lime & shale	840
shale	880
lime	940
sand	950
shale & lime	1010
sand	1028
shale	1070
lime	1090
shale & lime	1130
shale	1191
lime & shale	1300
lime	1420
lime & shale	1550
shale	1639
lime	1650
sand	1655
shale & lime	1752
shale	1887
dolomite & chert	1931
lime & shale	1988
sand & shale	2048
dolomite & chert	2165
Total Depth	

Cored 1996-2002, Rec. 4'

1' greenish gy fine grained slightly cal. shaley sand.
 2' greenish gy hrd fissile sdy shale w/stringers sand.
 6" greenish gy shaley fine grained calc. tight sand.
 4" wh fine grained frable sft sand.
 2" lgt gy fine grained hrd & tight quartzitic sand.

Tops:	
Tonoka	588
Oread	880
Lansing K. C.	1191
Marmaton	1639
Cherokee	1742
Viola	1887
Simpson	1931
Aruckle	2048
Run Schlumberger at total depth of 2165'	
Schlumberger T.D. 2164'	

2048
1191
-857
A.