

State Kansas County Marion

Company Messman-Rinehart Oil Company Well No. 1

Farm Oyer-Hobein Unit
(Henry)

Survey

Block No. Sec. 8 Twp. 19 S Range 5 E

Co-Ord. Elev. 1431' K/B
1429' D/F

NW	NE	SW
H. Hobein		
Oyer		

M-R Rig

32.8125% - A. A. Seeligson, Jr.
10.9375% - A. A. Seeligson, Sr.
21.875% - Chicago Group
21.875% - M-R Oil Co.
*12.5% - Lalicker & Scott
*-Subj. to Agreement w/L&S
dated 1/7/60

2300' Miss. test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
7/5/62		Location staked
7/29		Spd - 8-5/8" @ 189' w/143 sx
		2 gel., P.D. @ 8:30 p.m.
		7/29/62
8/8		M.I.R.T.
8/10	330-DD	Drilled plug (2:30 a.m.)
8/11	1070	Drlg. (#2 @ 950')
8/13	2000	Drlg. (#3 @ 1800')
8/14	2240	Conglomerate

Date	Depth	694315
11/3	2246	Miss. (-815')
11/11	2265	D.D.
D.S.T. #1	- 2243-65'	- Op 1½ hrs., GTS in 3'',
		Ga. 361,000 - 15''
		340,000 - 25''
		310,000 - 35''
		277,000 - 50''
		250,000 - 70''
		240,000 - 80''
		240,000 - 90''
		Rec. 75' mud in D.C.,
		BHP (30'') 820# - (40'') 675#
		FP 75-45#
8/15	D.S.T. #2	- 2265-2305' - Op 1 hr.,
		GTS in 5''
		Ga. 196,000 - 10''
		170,000 - 15''
		170,000 - 60''
		Rec. 170' gas-cut mud
		BHP (30'') 818-810#, FP45-82#
	2335'	Dr1g.
	2345'	R.T.D.
		4½'' @ 2343' w/50 sx.8/15/62
8/20	M.I.C.T. (Ran log),	Perf. 2255-75' w/
		4 ^s ft., Frac. 15,500 bbls. fluid,
		Prod. at rate of 1,024 Mcf, 580# &sg.
		Esti. 2,000 Mcfg open flow
8/30	C.S.Gas Co.	4-pt. open flow test:
		3,500,000 cfg/d
11/6	S.C.C. test:	1,109,000 cfg/d