

WICHITA BRANCH

KANSAS DRILLERS LOG

S. 30 T. 20S R. 10E E

API No. 15 — 111 — 20,211
County Number

Loc. SE SE SW


Operator
Little George Oil Co.

County Lyon

Address
680 Fourth Financial Center, Wichita, Kansas 67202

640 Acres
N

Well No. 1 Lessee Name Davis



Footage Location
330 feet from (N) (S) line 2310 feet from (E) (W) line

Principal Contractor Brandt Drilling Co. Geologist Charley V. Shank

Spud Date 6-18-76 Total Depth 2501 P.B.T.D. 2290'

Elev.: Gr. 1381

Date Completed 7-16-76 Oil Purchaser None

DF KB 1385

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9 1/4"	8 5/8"	20-24	44	Common	50	3% CaCl
Production	7 7/8"	5 1/2"	15 1/2	2494	Common	100	
				580 1719			

LINER RECORD None

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	Jet	2330-40'
			2	Jet	2222-24'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
200 gal. 15% reg. acid	2330-40'
250 gal. 10% mud Acid	2222-24'

INITIAL PRODUCTION

Date of first production Non-Commercial Prod. Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS
Oil bbls. Gas MCF Water bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Little George Oil Co.

30-20-10E

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Gas - Non-commercial

Well No. 1 Lease Name Davis

S 30 T 20S R 10E W SE SE SW

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Bartlesville Tested all water, NS	2330	2340		
Cattleman Tested water with a show of natural gas	2222	2224		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature
Operations Manager
Title
June 14, 1977
Date

July 2, 1976.

BRANDT DRILLING CO.

9505 WEST CENTRAL • SUITE 104 • (316) 722-5013
WICHITA, KANSAS 67212

30-20-10E

LITTLE GEORGE OIL #1 DAVIS
SE SE SW SEC 30-20S-10E
LYON COUNTY, KANSAS.


DRILLERS LOG

0 - 60	Lime cherty
60 - 145	Lime
145 - 162	Shale/lm streak
162 - 308	Lime/shale stks
308 - 430	Lime
430 - 458	Sandy lime
458 - 535	Lime
535 - 757	Shales/lm stk
757 - 800	Lime
800 - 927	Shales/Sandy
927 - 1010	Lime
1010 - 1063	Shales
1063 - 1097	Lime
1097 - 1102	Shales Black carbonaceous
1102 - 1136	Lime
1136 - 1421	Shales, sandy
1421 - 1705	Lime
1705 - 1715	Shales
1715 - 1828	Lime
1828 - 1940	Shales, sandy
1940 - 1955	Lime
1955 - 1975	Shales
1975 - 1988	Lime, dense
1988 - 2035	Shales/lm stks
2035 - 2098	Lime and shly lm

30-20-10 E

BRANDT DRILLING CO.

9505 WEST CENTRAL • SUITE 104 • (316) 722-5013
WICHITA, KANSAS 67212



2098 - 2101	Shale
2101 - 2146	Sand, shaly & sandy shale
2146 - 2155	Sand, micaceous
2155 - 2184	Shales, sdy
2184 - 2192	Lime
2192 - 2204	Shales, limey
2204 - 2221	Shales, gray & black
2221 - 2230	Sand, crse show gas.
2230 - 2280	Sand, water
2280 - 2301	Shales, black
2310 - 2338	Sand, shaley
2338 - 2372	Sand
2372 - 2484	Shales/ sand and lime stks
2484 - 2501	Lime
2501	RTD

