

URIC

XENIA CORPORATION

Operator Martin Oil Properties Address Norman, Oklahoma
 Lease Hastert Well No. 1-W
 Location Sec 13, Twp 20, Rge 20 E County Anderson
 Contractor Xenia Corporation API NO. 15-003-238870000
 Spud Date May 31, 1996 Date Reached TD June 3, 1996

Thickness of Strata	Formation	Total Depth
0 - 3	Soil	3
16	Clay & Gravel	19
39	Shale	58
30	Limestone	88
11	Shale	99
1	Limestone	100
3	Shale	103
1	Limestone	104
6	Shale (Red Bed)	110
43	Shale	153
14	Limestone	167
6	Shale	173
35	Limestone	208
6	Shale (Blk)	214
22	Limestone	236
3	Shale (Blk)	239
24	Limestone	263
4	Shale (Blk)	267
4	Limestone	271
122	Shale	393
5	Sand/Odor & Show Good	398
30	Sandy Shale	428
2	Limestone	430
6	Shale	436
3	Limestone	439
6	Shale	445
9	Limestone	454
2	Shale (Blk)	456
4	Shale (White)	460
8	Sandy Shale	468
4	Sand/Lt Odor	472
1	Shale (Blk)	473
28	Shale	501
1	Shale (Blk)	502
4	Shale	506
6	Limestone	512
15	Shale	527
3	Limestone	530
1	Shale (Blk)	531
1	Limestone	532
20	Shale	552

1997 FEB 13 P 12:58

XENIA CORPORATION

0

Operator Martin Oil Properties

Address Norman, Oklahoma

Lease Hastert

Well No. 1-W

Location Sec 13, Twp 20, Rge 20 E

County Anderson

Contractor Xenia Corporation

API NO. 15-003-238870000

Spud Date May 31, 1996

Date Reached TD June 3, 1996

Thickness of Strata	Formation	Total Depth
10	Limestone	562
16	Shale/Limy	578
9	Limestone	587
9	Shale (Blk)	596
10	Limestone	606
3	Shale (Blk)	609
33	Shale	642
1	Limestone	643
15	Shale	658
1	Limestone	659
9	Sandy Shale	668
2	Limestone	670
16	Shale	686
2	Coal	688
11	Shale	699
2	Limestone	701
4	Shale (Blk)	705
14	Sandy Shale (Limy)	719
5	Broken Sand/Lt Odor & Show	724
3	Broken Sand/Odor-Show Good	727
7	Sand/Odor & Show Good	734
1	Coal	735
63	Shale	798

TD