

June 13, 1972

Sec. 13-20-20 E.

Kent Drilling Co.

TELEPHONE 448-3762

GARNETT, KANSAS 66032

HASTERT OIL COMPANY

HASTERT NO. 8

10	Soil & Clay	10
121	Shale	131
22	Lime	153
65	Shale	218
12	Lime	230
	Shale	235
36	Lime	271
7	Blk. Shale	278
28	Lime	306
	Shale	309
	Lime	329
75	Shale	504
3	Lime	507
7	Shale	514
7	Lime	521
53	Shale	574
5	Lime	579
14	Shale & Shells	593
5	Lime	598
56	Shale & Shells	654
3	Lime	657
16	Shale & Shells	673
2	Lime	675
110	Shale	785
11	Lt. Shale	796
3	Lime	799
5	Oil Sand	804
5	Sandy Shale	809
16	Shale	825T.D.

We set 820.80' of 4" casing in this well and it is cemented to the surface. This well should be perforated from 799 to 804, this was a broken sand section with very little bleeding.

Dear Sir

There was a well drill
on this place about
1918 or 1920 and others that
I have no log
have you's got them if
so please send them
to me or any
information

Yours
Ch. Hastert

Info sent
8/7/72

