

Well I-3

Sec 2-20-20

Ross lease

Glenn Caldwell # 1-3

started August 22nd

Finished August 30th

1968 Poss

2	top soil	2
6	clay	8
2	river gravel	10
10	clay sand rock	20
31	shale	51
29	lime	80
71	shale	151
13	lime	164
5	shale	169
37	lime	206
9	shale	215
22	lime	237
4	shale	241
4	lime	245
2	shale	247
9	lime	256
167	shale	423
3	lime	426
3	shale	429
3	lime	432
2	shale	434
9	lime	443
54	shale	497
5	lime	502
15	shale	517
4	lime	521
24	shale	545
3	lime	548
25	shale	573
3	lime	576
39	shale dark	615
15	sandy shale	630
5	sand oil show	635
10	sandy shale	645
20	sand oil	665
10	sandy shale	675

cored 51 ft.  
 run 4' set at 634 ft.  
 run 2' tubing & washed down to 675 ft.  
 pulled 2' and Schuster run shot  
 pulled 4' pipe after shot  
 run 4' pipe back in and set at 634 ft.

set 51 ft. 6 1/4 drive pipe

