OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

April 8, 1980

We-Kan Resources, Inc.
Rt. 3
Garnett, Kansas 66032

Gentlemen:

Enclosed herewith are the results of tests run on the rotary core samples taken from the Parks Lease, Well No. 4, Anderson County, Kansas and submitted to our laboratory on March 26, 1980.

The core samples were sealed in plastic bags by a representative of the client. In examining this core, it is assumed that each sample represents one foot of core.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES

Sanford A. Michel

SAM/kas
5 c to Garnett, Kansas

Oilfield Research Laboratories

GENERAL INFORMATION & SUMMARY

Company We-Kan Resources, Inc. Lease Parks Well No. 4

Location -

Section 27 Twp. 20S Rge. 21E County Anderson State Kansas

Elevation, Feet	
Name of Sand	Squirrel
Top of Core	609.0
Bottom of Core	615.0
Top of Sand	610.0
Bottom of Sand	615.0
Total Feet of Permeable Sand	4.0

Distribution of Permeable Sand: Permeability Range Millidarcys	Feet	Cum. Ft.
0 - 4	3.0	3.0
4 & Above	1.0	4.0

Average Permeability Millidarcys	4.1
Average Percent Porosity	15.1
Average Percent Oil Saturation	25.2
Average Percent Water Saturation	56.2
Average Oil Content, Bbls./A. Ft.	285.
Total Oil Content, Bbls./Acre	1,707.

OILFIELD RESEARCH LABORATORIES

LOG

Name We-Kan Resources, Inc. Lease Parks Well No. 4

Depth Interval, Feet	Description
609.0 - 610.0	Gray shale.
610.0 - 611.0	Dark brown slightly shaly sandstone.
611.0 - 612.0	Brown shaly sandstone.
612.0 - 613.0	Gray shale.
613.0 - 615.0	Light brown shaly sandstone.
[illegible] - [illegible]	Light brown shaly sandstone

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1-B

Company We-Kan Resources, Inc. Lease Parks Well No. 4

Sample No.	Depth, Feet	Effective Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.	Feet of Sand		Total Oil Content	Perm. Capacity Ft. X md.
			Oil	Water	Total			Ft.	Cum. Ft.		
1	609.5	13.1	27	69	96	274	Imp.	1.0	1.0	274	0.00
2	610.5	15.7	32	44	76	390	6.0	1.0	2.0	390	6.00
3	611.5	15.5	37	36	73	445	3.9	1.0	3.0	445	3.90
4	612.5	17.8	5	61	66	69	Imp.	1.0	4.0	69	0.00
5	613.5	17.1	21	59	80	279	2.4	1.0	5.0	279	2.40
6	614.5	11.1	29	68	97	250	3.9	1.0	6.0	250	3.90

Oilfield Research Laboratories

SUMMARY OF PERMEABILITY & SATURATION TESTS


TABLE III

Company We-Kan Resources, Inc. Lease Parks Well No. 4

Depth Interval, Feet	Feet of Core Analyzed	Average Permeability, Millidarcys	Permeability Capacity Ft. x Md.
609.0 - 615.0	4.0	4.1	16.20

Depth Interval, Feet	Feet of Core Analyzed	Average Percent Porosity	Average Percent Oil Saturation	Average Percent Water Saturation	Average Oil Content Bbl./A. Ft.	Total Oil Content Bbls./Acre
609.0 - 615.0	6.0	15.1	25.2	56.2	285	1,707

K+E 10 X 10 TO THE CENTIMETER • 25 X 38 CM. KEUFFEL & ESSER CO. MADE IN U.S.A.



WE-KAN RESOURCES, INC.

PARKS LEASE WELL NO. 4

ANDERSON COUNTY, KANSAS

DEPTH INTERVAL, FEET	FEET OF CORE ANALYZED	AVERAGE PERCENT POROSITY	AVG. OIL SATURATION PERCENT	AVG. WATER SATURATION PERCENT	AVERAGE PERMEABILITY, MILLIDARCYS
609.0 - 615.0	6.0	15.1	25.2	56.2	4.1