

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY  
 UNION NATIONAL BANK BLDG., WICHITA, KANSAS


55300

CASING RECORD

LOCATION NE cor SE NW

SEC 29 T 20 R 17 E.

10" FARM Pierson NO. 1 COUNTY Coffey  
 20" 8 1-4 COMPANY Connell Oil Company.  
 15 1-2 6 5-3 CONTRACTOR  
 12 1-2 5 3-16 COMMENCED



TOTAL DEPTH SHOT QUARTS BETWEEN  
 CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Connell Oil Company,

El Dorado, Kansas.

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION D. & A.

REMARKS

Formation	Depth
soil, blk, soft	4
lime, light, hard	10
shale, blue, soft	24
lime, light, hard	34 - D
shale, light, soft	65
sand H2O gray, soft (H. F.)	125
shale, light, soft	180
lime, light, hard	185
sand, light, soft	225
shale, light, soft	370 - L
lime, light, hard	404
shale, blue, soft	409
lime, light, hard	460
shale, light, soft	590
lime, light, hard	630
shale, light, soft	645
lime, light, hard	650
shale, light, soft	675
lime, light, hard	750
shale, light, hard	760
lime, light, hard	780
shale, blk, soft (3 Bailers)	783
lime, light, hard	797 - BNC
shale, light, soft	952 - M
lime, light, hard	955
shale, light, soft	970
lime, hard	980
sand H2O, soft (Hole full)	1000
shale light, soft	1048
lime, light, hard	1053
shale, white, soft	1074
shale, blk, soft	1090
shale, blue	1107
lime, light, hard	1110
shale, soft, soft	1115
lime, light, hard	1123
shale, light, soft	1128 - C
lime, light, hard	1130 - CH
shale, blk, soft	1150
shale, light, soft	1170
sand, light, soft 4 B. W.	1185
shale, dark, soft	1237
sand, dry	1245
shale blue	1253
shale, dark	1293
shale, light, soft	1320
shale, dark, soft	1352
shale, dark, soft	1405
sand, dark, soft	1428
shale, dark, soft	1487
sand dark, soft (H2O)	1496 - M
lime Mississipp 11 Bailers	1522
sand break, soft	1526
lime, light, hard Hole full W.	1550

1173  
 180  
 993

1173  
 797  
 + 376  
 1173  
 952  
 + 221

462  
 770  
 1132

1173  
 1170  
 + 43

1496  
 1173  
 - 323

1173  
 - 377