


MAY 25 1973



LOG OF WELL

Sanders #1
NE NE SE
Section 11-21-16 E
Coffey County, Kansas

15-031-20212

Elev. KB 1122
GD 1118

OPERATOR: Cameron K. Reed

CONTRACTOR: Berentz Drilling Co.

Commenced w/Rotary 11-9-72
Completed w/Rotary 11-12-72

Casing: 8 5/8" - 109' cemented w/50 sx

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1972
CONSERVATION DIVISION
Wichita, Kansas

Soil	3
Shale & Lime	328
Lime (Lansing)	451
Shale	546
Lime (KC)	758
Shale	897
Lime (Pawnee)	908
Shale	935
Lime (Altamont)	944
Shale	998
Lime (Fort Scott)	1058
Shale	1454
Lime (Mississippi)	1576
Lime (Osage)	1768
Shale (Kinderhook)	1812
Misner Sand	1814
Tan to Brown Dolomite	1822
Lime (Viola)	1854
Sand (Simpson)	1874
Lime (Arbuckle)	1890 R.T.D.

Ran Gamma Ray Neutron Log

Sample Tops	
Lansing 328	+794
K C Lime	- 546 - 576
Pawnee 897	- 225
Altamont 935	- 187
Fort Scott 998	+ 124
Mississippi 1454	- 332
Osage 1576	- 454
Kinderhook 1768	- 646
Misner 1812	- 692
Viola 1822	- 700
Simpson 1854	- 732
Arbuckle 1874	- 752
T.D. 1890	- 768

Log Tops	
BKC	758
Miss	1454
Miss Os	1576
Kind	1698
Viola	1816
Simp	1858
Arb	1878
Td	1894

