

✓
WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


13-21-2E

Company- ANDERSON-PRICHARD OIL CORPORATION
Farm- Bartel No. 4

SEC. 13 T. 21 R. 2E
NE NE SE

Total Depth. 2877
Comm. 12-2-56 Comp. 12-8-56
Shot or Treated.
Contractor. Peel Brothers, Inc.
Issued. 2-9-57

County Marion
KANSAS



CASING:

8 5/8" 123' cem.
5 1/2" 2876' cem.

Elevation. 1468 RB

Production. 186 BOPD & no water
8 hr State Test

Figures indicate Bottom of Formations.

shale	50
shale, sand	90
shale, lime	680
shale	1480
shale, lime	1860
sand	1980
lime, shale	2105
lime	2360
lime, shale	2625
lime, shale, chert	2700
shale	2835
lime, shale	2877
Total Depth	

Tops:	Sample	Schlumberger
Douglas	-	1851
Lansing	-	2052
Mississippi	2628	2630
Kinderhook	2680	2680
Hunton	2828	2829
Maquoketa	2840	2840
R.T.D.	2875	2877

Drld cem & CO to 2854.
Perforated 2829-40 w/4 sh.ch.per.ft.

30 Min., filled up 950' oil, no wtr.
1 hr., " " 1975' " , " "
2 hrs., " " 2500' " , " "
3 hrs., " " 2775' " , " ". POP