STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

Lease Owner (Applicant) Deep Rock Oil Corporation Address Atlas Life Bldg., Tulsa 2, Okla.

Lease (Farm Name) Odaffer Well No. #10

Well Location 1070' N of S, 855' E of W, NW/4 Sec. 14 Twp. 21 Rge. 20 (E)-(W)

County Anderson Field Name (if any) Bush City Shoestring

Total Depth 794' Oil x Gas ____ Dry Hole ____

Was well log filed with application? No. If not, explain: ____

See well on back of Plugging Record

Date and hour plugging is desired to begin 8 A.M. 12/1/50.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.

(Use an additional sheet if necessary) ____

Name of the person on the lease in charge of well for owner ____

Clyde Crozier Address Garnett, Kansas

Name of Plugging Contractor Nickels Drilling Company

Address Garnett, Kansas

Invoice covering assessment for plugging this well should be sent to

Deep Rock Oil Corporation Address Box 127, Osawatomie, Kansas

and payment will be guaranteed by applicant.

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1950

PLUGGING
FILE SEC 14 T 21 R 20E
BOOK PAGE 47 LINE 34

Deep Rock Oil Corporation
Applicant or Acting Agent

Date 11/30/50

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

December 11, 1950

Well No. 10
Lease Odaffer
Description NW NE SW NW 11-21-20E
County Anderson
File No. 47-31

Deep Rock Oil Corporation
Box 127
Osawatomie, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. A. E. Daniel, 229 W. 7th, Garnett, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW NW

SEC. 14 TWP. 21 RGE. 20

Dry Hole _____ Abandoned Oil Well Yes Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. # 10 Lease Odaffer

Operator Deep Rock Oil Corp Address Atlas Bldg Tulsa2 Okla

Field Bush City County Anderson

Total Depth 794 Feet.

(Describe briefly the manner in which the well was plugged)

Cement from 794 to 600
Bridged at 150
Cement 3 sacks approx 10
Hole filled to top with soil and rock and leveled with surface

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1950

PLUGGING
FILE SEC 14 T 21 R 20E
BOOK PAGE 47 LINE 39

A. P. Daniel
District Conservation Agent


Date 12 - 8 - 50

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Anderson County. Sec. 14 Twp. 21 Rge. 20 (E) (W)

Location as "NE/CNW¼SW¼" or footage from lines 1070' N of S, 855' E of W, NW/4

Lease Owner Deep Rock Oil Corporation

Lease Name Odaffer Well No. #10

Office Address Atlas Life Bldg., Tulsa 2, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed June 23, 1944 19

Application for plugging filed 11/30/50 19

Application for plugging approved 19

Plugging commenced 12/1/50 19

Plugging completed 12/4/50 19

Reason for abandonment of well or producing formation Off location for use in waterflooding program.

If a producing well is abandoned, date of last production 11/27/50 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. R. Daniel

Producing formation Squirrel Sand Depth to top 764' Bottom 784' Total Depth of Well 794' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Gas Sand		743'	764'	6¼"		740'
Oil Sand	Oil	764'	784'	10"		20'6"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ..... feet to ..... feet for each plug set.

Hole was cemented from 794' T.D. to 600' with 44 sacks of cement
Bridge placed at 150'
3 sacks of cement placed on bridge.
Hole filled to surface with soil and stones.

See over for well log.

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1950
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Deep Rock Oil Corporation
Address Box 127
Osawatomie, Kansas

STATE OF Kansas, COUNTY OF Miami, ss.

T. N. Henderson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T.N. Henderson
1123 Brown Avenue, Osawatomie, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1950

Notary Public.

My commission expires Jan. 1, 1952

22-5133-s 9-48—10M

PLUGGING
FILE SEC 14 T 21 R 20E
BOOK PAGE 47 LINE 34

Thickness of Strata	Formation	Total Depth
0'	Soil	4'
10	Clay-Yellow	14
7	Shale-Blue	21
143	Shale-W	164
30	Lime-W	194
13	Shale-Blue	207
5	Lime-W	212
18	Shale-L	230
4	Lime-Gray	234
16	Shale-Drk.	250
5	Lime-W	255
2	Shale-Drk.	257
13	Shale-Blue	270
4	Lime-L	274
9	Shale-Drk.	283
45	Lime-L	328
4	Shale-Drk.	332-Water
4	Lime-L	336
4	Shale-Blk.	340-Water
18	Lime	358
2	Shale-Blk	360
16	Lime-L	376
18	Shale-L	394
146	Shale-L	540
2	Red Rock	542
18	Lime-L	560
60	Shale-L	620
5	Lime-W	625
15	Shale-L	640
5	Lime-W.	645
28	Shale-D	673
2	Lime-W	675
25	Shale-Drk.	700
4	Lime-W	704
8	Shale-W	712
3	Lime-	715
5	Shale-L	720
5	Shale-Blk	725-Water
5	Shale-Gray	730-
10	Shale-W	740-Set $6\frac{1}{4}$"
3	Shale-W	743
21	Gas Sand	764
20	Oil Sand	784
10	Shale-Drk	794