

3 050335

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-003.-NA
NW, SEC. 13, T 21 S, R 20 W@

3630 feet from S section line
5115 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
Operator: State of Kansas
Name & Address: (Bush City Field)

Lease Name Ewing A Well # V-28
County Anderson
Well Total Depth 700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 feet NA

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jayhawk Drilling Co License Number 5872
Address RT 2 La Cygne Mo 66040

Company to plug at: Hour: 2 PM Day: 29 Month: 12 Year: 19 86

Plugging proposal received from _____
(company name) _____ (phone) _____

were: 2" pipe on Bag packer w/cement
3/4" pipe inside 2" pipe.
Fish 3/4" pipe out of 2" pipe Fill w/cement
Run 1" pipe outside 2" pipe tag cement
Fill to surface w/cement

Plugging Proposal Received by Thomas J Walsh
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 PM Day: 30 Month: 12 Year: 19 86

ACTUAL PLUGGING REPORT Fished out 609 Ft of 3/4" pipe pushed
packer to 640 Ft, washed down 1" pipe outside 2"
pipe to 475 Ft hit cement. Filled 2" pipe w/8 sx
cement pulled 3/4" pipe pumped in 51 sx cement
outside 2" pipe.

on 12-31-86 checked cement at 3 Ft down hole
Remarks: Used pump truck rig time 30 Hrs cat time 3 Hrs
(If additional description is necessary, use BACK of this form.)

(did) did not) observe this plugging.

Signed Thomas J Walsh
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas