

3 101-74

198 R

MAY 19 1987
API NUMBER 15-003-NA

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE, SEC. 14, T 21 S, R 20 W/E
3300 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
Operator: State of Kansas
Name & Address: Bush City Shoe String

Lease Name Cochran Well # F-8
County Anderson 35.00
Well Total Depth 700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8" feet 20

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jayhawk Drilling License Number 5872

Address Route 2, LaCygne, Kansas 66040

Company to plug at: Hour: 4:00 pm Day: 18 Month: 5 Year: 19 87

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 2" pipe set on rag packer with cement, run 3/4" pipe inside 2" pipe to TD
and fill with cement. Run 1" pipe outside 2" to cement and fill with cement.

Plugging Proposal Received by Thomas J. Welsh
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 11:00 am Day: 19 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT On 5-18-87, ran 3/4" pipe inside 2" pipe to 640'. Filled with
13 sacks cement. Ran 1" pipe outside 2" pipe to 300'. On 5-19-87, tagged cement
inside 2" pipe at 200', filled with 7 sacks cement. Pumped 75 sacks outside 2"
pipe from 300'. On 5-20-87, tagged cement at 20', filled with 8 sacks cement.
Back hoe time, 4 hours. Used pump truck.

STATE CORPORATION COMMISSION

MAY 27 1987

Remarks: Total cost: \$2,032.38
(If additional description is necessary, use BACKWORK FORM.)

I (did / ~~did not~~) observe this plugging.

Signed Thomas J. Welsh
(TECHNICIAN)