

3 150507

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-003-NA
NE, SEC. 14, T 21 S, R 20 W(E)

2805 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Lease Name Ewing A Well # A-30

Operator: state of kansas

County Anderson

Name & Address (Bush city field)

Well Total Depth 700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 feet NA

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jayhawk Drilling License Number 5872

Address RT 2 LaCyane Ks 66040

Company to plug at: Hour: 2 PM Day: 6 Month: 1 Year: 19 87

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 8" pipe set on Bay packer w/cement

3/4" pipe inside 2" on packer

Pull 3/4" pipe out of 2" pipe Fill with cement

Run 1" pipe outside 2" pipe tag cement

and then Kill to surface w/cement

Plugging Proposal Received by Thomas Walsh
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6 PM Day: 7 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT pulled 588 ft of 3/4" pipe pushed packer

to 451 ft Run 1" pipe outside 2" pipe to 450 ft

Fill 2" pipe with 8 SX cement pump through 3/4" pipe

pumped in 45 SX cement out side 2" pipe on 1-7-86

tagged cement @ 360 ft took 101 SX cement to

fill to surface

Remarks: used pump truck Rig time: 25 HRS Cat time 3 HRS
(if additional description is necessary, use BACK of this form.)

(did) did not) observe this plugging.

Signed Thomas Walsh
(TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas