

3 05 1886

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-003-NA
NE, SEC. 14, T. 21 S, R. 20 W

3795 feet from S section line
725 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
Operator: State of Kansas
Name & Address: (Bush City Field)

Lease Name Ewing A Well # W-33
County Anderson
Well Total Depth 700 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 feet NA

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jayhawk Drilg Co License Number 5872

Address RT 2 LaCygne Mo 66048

Company to plug at: Hour: 12 PM Day: 2 Month: 1 Year: 19 87

Plugging proposal received from _____
(company name) _____ (phone) _____

were: 2" pipe inside 4" pipe set on packer
4" pipe on rag packer w/cement
pull 2" pipe Run 1" pipe inside 4" pipe
Fill w/cement Run 1" pipe outside 4" pipe
rag cement and Fill to surface w/cement

Plugging Proposal Received by Thomas J Walsh
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 PM Day: 5 Month: 1 Year: 19 88

ACTUAL PLUGGING REPORT pulled 2" pipe Run 1" pipe inside
4" pipe Filled with 39 SX cement Run 3/4"
pipe outside 4" pipe hit cement @ 120 Ft
Filled to surface with 10 SX cement Tagged
cement inside 4" pipe @ 40' Ft Filled to surface
w/ 7 SX cement Pulled top joint of 4" pipe (30ft)

Remarks: Used pump truck Big time 26 HRS cat time 3 Hrs
(If additional description is necessary, use BACK of this form.)

(did) did not) observe this plugging.

Signed Thomas J Walsh
(TECHNICIAN)