

3 05 18 87

JAN 29 1987

30
R

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-003-NANW, SEC. 14, T. 21 S, R. 20 WE4455 feet from S section line4620 feet from E section lineLease Name Odaffer Well # 1-ICounty AndersonWell Total Depth 700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 feet NA

TECHNICIAN'S PLUGGING REPORT

Operator License # _____

Operator: State of KansasName & Address (Bush City Field)Abandoned Oil Well ☒ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jayhawk Drilg License Number 5872Address RT 2 LaCygne KS 66040Company to plug at: Hour: 8AM Day: 28 Month: 1 Year: 19 87

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 2" pipe cemented in on Bag Packer with
3/4" pipe inside on packer Fish 3/4" pipe out
clean out inside 2" wash down outside 2" pipe to
cement. Fill inside and outside 2" pipe
with cement

Plugging Proposal Received by Thomas J Walsh
(TECHNICIAN)Plugging Operations attended by Agent?: All ☒ Part _____ None _____Operations Completed: Hour: 12 PM Day: 29 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT Fished out 3/4" pipe 630ft clean out
to 660 ft washed down outside 2" pipe to 460ft
pumped 25 SX cement inside 2" pipe Filled outside
2" pipe w/115 SX cement. Tagged cement @ 60ft Filled w/30
SX cement

Big time 29 Hrs cat time 4 HrsRemarks: used pump truck

(if additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE _____

INV. NO. _____

FEB 1 1987

Signed

Thomas J Walsh
(TECHNICIAN)CONSERVATION DIVISION
WICHITA, KANSASFORM CP-2/3
Rev. 01-84