

3 050538

JAN 22 1987

31K

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-003-NA
SE, SEC. 14, T 21 S, R 20 WE

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
990 feet from E section line

Operator License # _____

Lease Name Farlow Well # 0-35

Operator: state of Kansas

County Anderson

Name & Address (Bush City Field)

Well Total Depth 700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 feet NA

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jayhawk Drilg License Number 5872

Address RT 2 LaCygne Mo 66040

Company to plug at: Hour: 8:30 AM Day: 22 Month: 1 Year: 1987

Plugging proposal received from Tom Maylan

(company name) _____ (phone) _____

were: 2" pipe cemented in on May packer with 3/4" pipe inside on a packer Fish 3/4" pipe out clean out inside 2" wash down outside 2" pipe to cement Fill inside and outside 2" pipe with cement

Plugging Proposal Received by Thomas J Walsh
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 PM Day: 22 Month: 1 Year: 1987

ACTUAL PLUGGING REPORT Fish out 609 Ft 3/4" pipe left packer in hole wash down outside 2" pipe Filled 2" pipe with 125x cement Filled outside 2" pipe from 200 Ft to surface w/ 585x cement w/ pump truck
Big time 29 HRS
opt time 7 HRS

Remarks: Had to build crossing across a creek
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE _____

INV. NO. _____

STATE CORPORATION COMMISSION
FEB 17 1987 Signed Thomas J Walsh
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas