

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA, KANSAS 67202

FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
MAY 16 1967
CONSERVATION DIVISION
WICHITA, KANSAS

Lease Owner Tex-Kan Oils Inc.

Address Box 2108, Fort Worth, Texas

Lease (Farm Name) Odaffer

Well No. W-5

Well Location N 1/4 NW 1/4 Sec. 14 Twp. 21 Rge. 20E (E) (W)

County Anderson Field Name (If Any) _____

Total Depth 865 Oil Well oil Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Well Log filed with application no or Well Log filed with Plugging Supervisor _____
will be filed with plugging report.

Date and hour plugging is desired to begin May 16, 1967 9:AM.

Plugging of the well will be done in accordance with the Rules and Regulations of the State
Corporation Commission.

Name of company representative in charge of plugging operations _____

Ray Marmor

Address Garnett, Kansas

Plugging Contractor Jackson & Eastwood

License No. 613

Address Bronson, Kansas

Invoice covering assessment for plugging this well should be sent to _____

Tex-Kan Oils Inc.

Address Box 2108, Fort Worth, Texas.

and payment will be guaranteed by applicant.

Signed: Ray Marmor
Applicant or Acting Agent

Date: May 16, 1967



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

May 19, 1967

WELL PLUGGING AUTHORITY

Tex-Kan Oils, Inc.,
Box 2108
Ft. Worth, Texas 76101

Well No.	N-5
Lease	Odaffer
Description	NW NW NW 14-21-20E
County	Anderson
Total Depth	NW NW NW 14-21-20E
Plugging Contractor	Jackson & Eastwood Bronson, Ks.

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

A handwritten signature in cursive script, reading "J. P. Roberts".
J. P. Roberts, Administrator

Mr. O. D. Garrett - R. R. #1 - Wellsville, Ks. 66092
is hereby assigned to supervise the plugging of the above
named well.

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
MAY 28 1967
STATE CORPORATION COMMISSION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Marmon of Tex-Kan Oils Inc. has this
date requested permission to plug the following described well:

Mr. Marmon guarantees payment of the plugging fee.

Operator's full Name: Tex-Kan Oils Inc.

Complete Address: Box 2108, Fort Worth, Texas.

Lease Name: Odaffer Well No. F-5

Location: N. 14. NW Sec. 14 Twp. 21 Rge. 20 (E) (W)

County Anderson Total Depth 865 Oil Well oil

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Marmon was instructed to plug the well as follows:

Set plug packer in 2" at 765' and run 1 sack cement,
shoot pipe off and mull, fill to 215' and bridge with
brush and rock and run 10 sacks cement, fill to 30' and
bridge with brush and rock and run 4 sacks cement, fill
to surface with soil.

Very truly yours,

C. D. Garrett
Conservation Division Agent

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
DIVISION OF CONSERVATION
MAY 22 1967
WICHITA, KANSAS

Operator's Full Name Tex-Kan Oils Inc.
Complete Address: ^{Box} 2108, Fort Worth, Texas. 76101
Lease Name Odaffer Well No. M-5
Location NE NW Sec. 14 Twp. 21 Rge. 20E (E) (W)
County Anderson Total Depth 865
Abandoned Oil Well oil Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Jackson & Eastwood
Address: Bronson, Kansas License No. 613
Operation Completed: Hour 3:PM. Day 17 Month May Year 1967

The Above well was plugged as follows:

2" was cemented in with 20 sacks cement, set plug nacker in 2" at
765' and ran 1 sack cement, shot 2" off at 380' and milled, filled
to 215' and bridged with brush and rock and ran 10 sacks cement,
filled to 30' and bridged with brush and rock and ran 4 sacks cement,
filled to surface with soil.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

DATE 5-19-67
INV. NO. 6475-E

9P

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Anderson County, Sec. 14 Twp. 21 Rge. 20 (E) (W)

Location as "NE/CNW/SW" or footage from lines. N.W. N.W. N.W.

Lease Owner Tex-Kan Oils Inc.

Lease Name Odaffer Well No. N-5

Office Address Box 2108, Fort Worth, Texas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 9-23-64 19

Application for plugging filed 5-6-67 19

Application for plugging approved 5-6-67 19

Plugging commenced 5-16-67 19

Plugging completed 5-17-67 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 5-9-67 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well O. D. Garrett

Producing formation Squirrel Depth to top Bottom Total Depth of Well 865 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

2" pipe, cemented in with 20 sacks of cement, plug-packer set in 2" pipe at 765'.
Ran 1 sack cement on plug-packer. 2" pipe shot off at 370' and pulled, XXXXXXXX
XXXXXX XXXXXXXX XXXXXXXX XXXXXXXX XXXXXXXX XXXXXXXX XXXXXXXX XXXXXXXX
filled to 215' and bridged. Ran 10 sacks of cement, filled to 30' and bridged.
Ran 4 sacks cement, filled hole to surface with top soil.

Log on back

RECEIVED
STATE CORPORATION COMMISSION

MAY 26 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jackson and Eastwood

Address Bronston, Kansas

STATE OF KANSAS COUNTY OF ANDERSON ss.

RAY MARMON (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ray Marmmon

Box 351, Rt #1, Garnett, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of MAY, 19 67

My commission expires MAY 22, 1969

Notary Public.

Log Formation for Odaffer N-5

Soil	1
Gravel	13
Lime	23
Shale	181
Lime	210
Shale	258
Lime	265
Shale	283
Lime	292
Shale	299
Lime	338
Shale	345
Lime	365
Shale	373
Lime	386
Shale	572
Lime	580
Shale	638
Lime	645
Shale	663
Lime	668
Shale	689
Lime	703
Shale	725
Lime	729
Shale, Dk.	739
Lime	741
Shale	743
Lime	744
Shale, Dk.	749
Shale, Lt.	753
Shale, Gray,	763
Sand & Shale	820
Sand Oil	820
Shale	865