

Company Claude Crowder

Sec. 26 T. 21 R. 21E

Farm Jefferies


No. 5

Loc. NW/4

County Linn

Total Depth
Comm. Jan 26, 1936
Shot or Treated
Contractor
Issued

Comp.



	Casing	
20 in.	10 in	
15 1/2	8 1/4	
12 1/2	6 5/8	
13 3/8	5 3/16	

Elevation

Production

Figures Indicate Bottom of Formation

*Gift From
Claude Crowder*

3	Soil	3	
11	Clay	14	
2	River Gravel	16	Water
4	Lime	20	
3	Sandy Lime	23	
21	Lime	44	
1	Shale Black	45	
45	Lime	90	
125	Blue Shale	215	
5	Lime Shells	220	
30	Shale Light	250	
2	Lime Shells	252	
10	Shale	262	
8	Red Bed	270	
18	Lime	288	
52	Blue Shale	340	
20	Lime	360	Reduced 6 1/4 at 360'
10	Shale Blue	370	
4	Lime	374	
7	Shale Blue	381	
7	Lime	398	
12	Sandy Shale	410	
10	Blue Shale	420	
10	Lime	430	
6	Shale	436	
10	Lime	446	
5	Shale Blue	451	
11	Lime	462	
15	Shale White	477	
	Reduced 4 7/8 at 477'		
8	Shale White	485	
7	Shale Sandy	492	
22	Sand Gas Showing	514	
2	Shale Blue	516	
29	Shale Blue	545	
2	Lime	547	
7	Shale Dark	554	
54	Shale Light	608	
1	Lime	609	
47	Shale Blue	656	

Bottom

Company

Farm

JEFFRIES

No. 5

Sec. 26 T. 21 R. 21E

Loc. N.W. 1/4

County

Total Depth


Comm.

Shot or Treated

Contractor

Issued

Comp.



Elevation

Production

Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Figures Indicate Bottom of Formation

Set 28 8 1/4 casing 360 6 1/4 casing
 645 2" rubber tube packer
 set packer 4 7/8 rubber at 480
 set 165 feet 2" anchor pipe
 Bolt in anchor pipe 498
 Error in original log
 at 260' 10' shale made 270'

Get From
Claude Crowder