

D. W. JEFFERS FARM WELL NO. # 5

Started Jan. 25th. 1936.

3'	Soil	3			
11'	Clay	14			
2'	River gravel	16	water	Set 28'	8 1/2" casing Not pulled
4'	Lime	20		Set 360'	6 1/2" " Pulled
3'	Sandy lime	23		" 467'	4 7/8 " "
21'	Lime	44		" 645'	2" tube
1'	Shale-black	45			
45'	Lime	90			
120'	Blue shale	215		Set Pa cker	4 7/8 a t 480' Rubber
5'	Lime shale	220		" 165'	2" a nchor pipe
30'	Shale-light	250			
2'	Lime shale	252			
10'	Shale	262			
8'	Red bed	260			
18'	Lime	278			
52'	Blue shale	330			
20'	Lime	350			
10'	Shale-blue	360			
4'	Lime	364			
17'	Shale-blue	381			
7'	Lime	388			
12'	Sandy shale	400			
10'	Blue shale	410			
10'	Lime	420			
6'	Shale	426			
10'	Lime	436			
5'	Shale-blue	441			
11'	Lime	452			
15'	Shale-white	467			
8'	Shale-white	475			
7'	Shale-sandy	482			
24'	Sand - Gas	504			
2'	Shale-blue	506			
29'	Shale-blue	535			
2'	Lime	537			
7'	Shale-dark	544			
54'	Shale-light	598			
1'	Lime	599			
47'	Shale-blue	645			
	Bottom				

D. W. Jeffers - Description

Northwest quarter
 Section 26
 Range 21
 Township 21

D. W. JEFFERS FARM WELL NO. # 5

Started Jan. 25th. 1966



3'	Soil	3
11'	Clay	14
2'	River gravel	16
4'	Lime	20
3'	Sandy lime	23
21'	Lime	44
1'	Shale-black	45
45'	Lime	90
120'	Blue shale	215
5'	Lime shale	220
30'	Shale-light	250
2'	Lime shale	252
10'	Shale	262
8'	Red bed	260
18'	Lime	278
52'	Blue shale	330
20'	Lime	350
10'	Shale-blue	360
4'	Lime	364
17'	Shale-blue	381
7'	Lime	388
12'	Sandy shale	400
10'	Blue shale	410
10'	Lime	420
6'	Shale	426
10'	Lime	436
5'	Shale-blue	441
11'	Lime	452
15'	Shale-white	467
8'	Shale-white	475
7'	Shale-sandy	482
24'	Sand - Gas	504
2'	Shale-blue	506
29'	Shale-blue	535
2'	Lime	537
7'	Shale-dark	544
54'	Shale-light	598
1'	Lime	599
47'	Shale-blue	645
	Bottom	

water

Set 28' 3 1/4" casing Not pulled
 Set 360' 6 1/4" " Pulled
 " 467' 4 7/8" "
 " 645' 2" tube
 Set Packer 4 7/8 at 480' Rubber
 " 165' 2" anchor pipe
 Bolt in anchor pipe 498' .

D. W. Jeffers - Description

Northwest quarter
 Section 26
 Range 21
 Township 21