

NW 1/4 26-21-21 LimCo

Well # 5

Jan 26 - 1936

3	Sail	3
11	Clay	14
2	River gravel	16
4	lime	20
3	sandy lime	23
21	lime	44
1	Shale black	45
45	lime	90
120	blue shale	215
5	lime shells	220
30	Shale light	250
2	lime shells	252
10	Shale	262
8	Red bed	280
18	Lime	288
52	blue shale	340
20	lime	360
10	shale blue	370
4	lime	374
17	shale blue	381
7	lime	398
12	sandy shale	410
10	blue shale	420
10	lime	430
6	shale	436
10	Lime	446
5	shale blue	451
11	lime	462
15	shale white	477
	Reduced $4\frac{7}{8}$ at 467'	
8	shale white	485
7	shale sandy	492
22	sand Gas showing	514
2	shale blue	516
29	shale blue	545
2	lime	547
7	shale dark	554
54	shale light	608
1	lime	609

water

Reduced $6\frac{1}{4}$ at 360'

Should be 477

47 shale blue
Bottom

656

Set 28
360
645

$8\frac{1}{4}$ casing
6 $\frac{1}{4}$ "
2" tube Rubber Packers.

Set Packers $4\frac{1}{8}$ rubber at 480

Set 165 feet 2" Anchor pipe

Bolt in Anchor Pipe 498

Error in original log
at 260'

10' shale made 270'