


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - THE TEXAS COMPANY
Farm - A. N. Smith (Dove) No. 3-W

SEC. 10 T. 21 R. 22E
NW SE SE NW
Approx. 600' fr S1 & 500' fr
El of E $\frac{1}{2}$ NW
County. Linn

Total Depth. 524 $\frac{1}{2}$ ' PB513:
Com'n. 2-4-47 Comp. 11-26-48
Shot or Treated. Shot SNG 21 qts. 492' to 513'
Contractor. Shevemaker
Issued. 9-25-48

KANSAS



CASING:
8-5/8" 20'
7" 456' P.

Elevation. _____

Production. Water Input

Figures Indicate Bottom of Formations.

soil	2
clay	10
gravel	12
lime shells	14
shale	20
lime	61
shale	66
lime	83
shale	91
lime	94
shale	100
lime	113
shale	270
lime	275
shale	286
lime	290
shale	292
lime	300
shale	351
lime	364
shale	366
lime	369
shale	377
lime	382
shale	384
slate	388
shale blue	392
shale drk	410
lime	418
shale	421
lime	424
shale	431
lime	437
shale drk	439
lime	442
slate	451
lime	455
shale	473
shale green sdy	512
shale blue sdy	521
slate	524 $\frac{1}{2}$
Total Depth	

Plugged Back to 513'

Cored, 504-524 $\frac{1}{2}$
Top Squirrel Sand 504'
Packer 487'