

19-21-23 E

WELL LOG

COMPANY A. J. Stormfelts

FARM Russell McGrew #1

LOCATION - SE-SW-SE

Sec 19, T 21s, R 23e

Linn County, Kansas

TOTAL DEPTH 502 ft.

COMP. March 14, 1962

DEPTH

Top soil	6	
Lime	38	
Shale Blk	43	
Lime	69	
Slate	70	
Lime	85	
Shale	87	
Lime	92	
Shale	240	
Lime	248	
Shale Sandy	268	Alt
Lime Hard	282	
Shale	301	
Lime	304	
Shale	336	Band
Lime	348	
Shale	352	
Lime	354	Pow
Shale	380	
Lime	366	
Shale Dark	399	Gas
Lime	424	FS
Shale Dark	434	
Lime	436	
Shale	465	
Sand Broken	467.5	S.L.M.
Set 6 5/8" Casing		

CORE LOG

Broken Sand	470	Gas
Sand	472.9	Gas Oil T
Broken Sand	476.8	
Broken Sand	480.7	Oil Show
Broken Sand	483.2	Oil Show
Broken Sand	486.4	Oil Show
Black Sand	489.9	Oil Show
Shale	492.6	
Shale	502.8	T. D.

PLUGGING RECORD

March 14, 1962

8 sacks cement on bottom.
 Filled to 85 ft. and bridged
 with brush and rock and 3
 sacks cement.
 Filled to 90 ft. and bridged
 with brush and rock and 3
 sacks of cement.
 Rock and soil to surface.

Set 6 5/8" Casing