

Company *Evans & Crowder*

Farm *Switzer*

No. *2*

*27-21-23 E*  
Sec. 27 T. 21 R. 23 E  
Loc. *NE SW*  
County *Linn*

Total Depth *488*


Comm.

Comp. *June, 1944*

Shot or Treated

Contractor

Issued



Casing

20 in.	10 in.
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16

Elevation

Production *100 M gas*

Figures Indicate Bottom of Formation

soil	2	
gravel	9	
lime	40	
shale	45	
lime	70	
shale	75	
lime	97	<i>H</i>
shale	245	
lime	255	
shale	275	
lime	290	
shale	348	<i>Bind</i>
lime	360	
shale	372	<i>Pwr</i>
lime	377	
shale black	408	<i>gas</i>
lime	428	<i>FS</i>
slate black	434	
shale dark	444	
shale light	461	
✓ sand gas	473	
shale	488	<i>bottom</i>

Packer set *455*

Perforation set *468 (20 feet from bottom)*

*6 3/4 x 2" robison*