


20" 10" 1565 FARM Allison NO. 2 COUNTY Marion
 15 1-2 8 1-4 COMPANY C.L. Sheedy & Empire Gas and Fuel.
 12 1-2 950 6 5-8 2248 CONTRACTOR
 5 3-16 2390. COMMENCED 9-5-25 COMPLETED 10-20-25
 TOTAL DEPTH 2394 SHOT QUARTS BETWEEN



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Empire Gas and Fuel.

Eldorado, Kansas.

(CORRECTED COPY)

ELEVATION 1374

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 150 Bbls.

REMARKS

Formation	Depth	Formation	Depth.
lime shells	20	slate white soft	1250
lime light hard	60	lime white hard	1270
slate blue soft	70	2 Bailers water	1260
lime light hard	100	lime white hard	1285
slate blue soft	150	slate grey soft	1300
red rock soft	160	lime white hard	1310
lime light hard	200	slate white soft	1320
slate blue soft	220	lime white soft	1370
lime light hard	250	slate dark soft	1335?
1 B.W. at 230		lime white hard	1435?
shale light soft	370	slate white soft	1430
slate blue soft	400	lime white hard	1460
lime light hard	450	2 Bailers water	1450
shale light soft	490	lime sdy brown	1475
lime light hard	540	lime white hard	1485
slate blue soft	600	slate dark soft	1515
lime light hard	640	lime white hard HFW	1540
1 Bailer water at 620 cave		lime sandy grey	1555
slate blue soft	650	slate blue soft	1560
red rock soft	675	slate dark soft	1565
lime light hard	700	slate blue soft	1615
shale blue soft	740	lime brown hard	1640
lime white hard	750	lime brown hard	1650
slate brown soft cave	790	slate soft	1690
lime white hard	800	lime white hard	1730
slate brown soft	850	lime brown hard	1800
lime white hard	870	lime white hard	1905
red rock soft	880	slate blue soft	1920
lime shells white	900	lime white hard	1955
slate brown soft	930	slate white soft	1960
sand white soft HFW	940	lime white hard	1990
lime dark hard	955	slate blue soft	1995
slate blue soft	965	lime white hard	2035
lime white hard	985	slate white soft	2100
slate blue	1000	shalecave soft	2110
lime white hard	1020	lime brown hard	2118
slate blue	1035	lime sandy brown	2140
lime white hard	1045	slate black soft	2150
slate blue soft	1075	lime white hard	2165
lime white hard	1120	slate blue soft	2180
slate white soft	1130	lime white hard sdy	2210
lime white hard	1160	3PW 2210	
slate blue soft	1175	lime white hard sdy	2230
lime white hard	1200	red rock soft	2240
lime white hard	1210	lime white hard	2250
slate white soft	1230	slate blue soft	2260
lime brown hard	1240	slate blue soft	2270
		slate green soft	2275
		slate blue soft	2325
		slate blue soft	2350
		slate dark soft	2390
		sand oil pay	2394 S.L.M.