

Mid-Continent Petroleum Corporation
Formerly Cosden & Company

PRODUCERS AND REFINERS OF
HIGH GRADE PETROLEUM

ADDRESS ALL COMMUNICATIONS TO THE COMPANY

TULSA, OKLA.

El Dorado, Kansas.
August 7th, 1928.

Mr. M. A. Benear,
P. O. Box, #2025,
Tulsa, Oklahoma.

Dear Sir: -

The Tulsa Oil Co and G. W. Gasche test, located in the Northwest corner of Section 27-21-12E Lyon County, Kansas, have completed their contract with our company.

This well had dry sandy shale from 1821-1838' this is a little correction from what I phoned in as we got the samples mixed up, they also had seven feet of dry sand from 1910-1917' and Top of the mississippi lime at 2039' steel line measurement, total depth is 2089 feet without a break or any water. It is being plugged at this depth.

Our contract called for 2000 feet.

Yours very truly,

Chas Sherwood.

G. W. GASCHE No. 1.

NW Corner NW $\frac{1}{4}$ Sec. 27, T. 21, R. 12, Lyon Co. Kans.

Operator: G. W. Gasche. Contractor, LaDow Gas Co.

Casing: 10'-15 $\frac{1}{2}$ ", 70-10, 495'-12 $\frac{1}{2}$ ", 52-495; 1005'-10";

~~40-1005; 1538'-8", 24-1538; 1815'-6 5/8", 20-1815.~~

Strata	Thick- ness	Total Depth	Strata	Thick- ness	Total Depth
Soil	10	10	Lime	30	920
Lime	4	14	Sand	27	947
Shale	16	30	Shale	8	955
Lime	15	45	Sand	37	992
Shale	5	50	Lime	28	1020
Lime	15	65	Shale-dark	8	1028
Shale-light	10	75	Lime	10	1038
Shale-blue	48	123	Shale-white	4	1042
Lime	4	127	Lime-hard W. 4 b. @		
Shale-brown	73	200	1115-25	133	1175
Lime	5	205	Shale-light	33	1208
Shale-brown	4	209	Lime	7	1215
Lime	8	217	Shale-dark	10	1225
Shale-dark	70	287	Lime	10	1235
Lime	40	327	Shale-white	5	1240
Shale-dark	23	350	Lime	10	1250
Lime	5	355	Shale-blue	20	1270
Shale-brown	25	380	Lime	75	1345
Lime	10	390	Shale-dark	10	1355
Shale-brown	5	395	Lime	45	1400
Shale-green	7	402	Shale-light	10	1410
Lime	5	407	Shale-brown	125	1535
Shale-blue	13	420	Lime	10	1545
Lime	5	425	Shale-light	5	1550
Shale-light	17	442	Lime	5	1555
Lime	10	452	Shale-brown	2	1557
Shale-light	18	470	Lime	18	1575
Lime	7	477	Shale-brown	30	1605
Shale-dark	10	487	Lime	15	1620
Shale-brown	93	580	Shale-brown	12	1632
Lime	15	595	Lime	10	1642
Shale-blue	5	600	Shale-dark	13	1655
Lime	32	632	Lime	8	1663
Shale	5	637	Lime shells	32	1695
Lime	20	657	Shale-dark	137	1825
Shale-white	23	680	Sand-Bartlesville	13	1838
Lime	2	682	Sand-brooken	42	1880
Shale-white	10	692	Shale-dark	20	1900
Shale-brown	133	825	Shale-white	10	1910
Lime	10	835	Sand	7	1917
Shale-blue	5	840	Shale-dark	122	2039
Sand-H. F. Water	50	890	Lime Miss.	50	2089

Fredonia, Kans. August 7, 1928.

G. V. LaDow, of lawful age, having been first duly sworn, deposeth and saith; that he is the vice-president of The LaDow Gas Company; That on July 3, 1928, said LaDow Gas Company spudded in a prospect well for oil or gas in the northwest corner of Section 27-21-12, Lyon County, Kansas, according to a contract between said LaDow Gas Company and G. W. Gasche of Hartford, Kansas; That said well was completed August 5, 1928 and that the above is a true and accurate copy of the log of said well. Further the deponent saith not.

Subscribed to in my presence and sworn to before me this 7th day of August, 1928.

G. V. LaDow
Notary Public

My Commission Expires

My Commission expires May 16, 1929