


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORP.
Farm- L.D. Slocombe No. 2

SEC. 19 T. 21 R. 3E
SE NW SE.

Total Depth. 2817'
Comm. 4-5-57 Comp. 4-12-57
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 6-29-57

County Marion
KANSAS



Elevation. 1121' RB.

Production. 113 BOPD / 28% wtr.
State Phy. 8 hr.

Figures indicate Bottom of Formations.

surface soils	207
lime	300
lime-shale	515
shale	1240
shale-lime	1470
lime	1660
shale-lime	1828
sand	1873
shale	2070
lime	2567
chert	2645
lime-shale	2650
lime	2670
shale	2817 RTD
shale	2825
Total Depth	
TOPS: Sample	
Mississippi	2567
Kinderhook	2672
Hunton	2807
RTD	2817
CTD	2825

CO to RTD 2817. 1 hr., filled up 650' oil;
2 " " " 1200' "
4 " " " 1800' "

Swbd 112 BO / no wtr/11 hrs.
CO 2' of shale to RTD 2815. Hole filled to 1600'
Drl'd 2' shale & 3' lime. Hole filled 2200'
Swbd 60 BF in 6 hrs., no wtr.
Hole swbd down to 2000'. Ran bailer. Rec. 300'
HMCO & 500' wtr. CO hole. Swbd 48 BF / 5 BW/4 hrs.
POP.