


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORP.
Farm- L.D. Slocombe No. 3

SEC. 19 T. 21 R. 3E
NW SW SE

Total Depth. 2895'
Comm. 4-14-57 Comp. 4-22-57
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 6-29-57

County Marion
KANSAS



Elevation. 1133' RB

CASING:
8 5/8" 207' cem.
5 1/2" 2894' "

Production. 24 hr. State Test:
33 BO / 69 BWP.

Figures indicate Bottom of Formations

surface soils	207
lime-shale	840
shale	1240
shale-lime stks	1600
shale-lime	1818
sand	1898
lime-shale	1980
lime	2350
lime-shale	2550
lime	2680
shale	2829
Core #1	2836
Core #2	2844
Core #3	2850
lime	2895
Total Depth	

TOPS:	SAMPLE	SCHL.
Conglomerate	2579	2578
Mississippi	2598	2600
Kinderhook	2690	2693
Hunton	2828	2830

Diamond Core #1: 2829-36. Full Rec.
" " #2: 2836-44. " "
" " #3: 2844-50. " "

DST #1: 2828-44. Open 45 min. SI 20 min. Strong blow died in 35 min. Rec. 120' free oil & 1780' muddy oil & 625' wtr. IFP 168 # FFP 1015#. BHP 1015#.

DST #2: Straddle Packer 2859 & 2871. Open 1 hr. SI 20 min. Strong blow diminishing to zero in 50 min. Rec. 2330' salt wtr. IFP 240#. BFP 1400#. BHP 1400#.

Perf; 2830-34. w/4 jet ch per ft. Bailed 6 GOPH for 5 hrs., no wtr. Az w/250 gal. Swbd back load. Swbd 50 BO / 98 BW/16 hrs. POP.