


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORPORATION
Farm- L. D. Slocombe No. 4

SEC. 19 T. 21 R.3E
NW SE SE

Total Depth. 2834
Comm. 5-9-57 Comp. 5-18-57
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 6-29-57

County Marion
KANSAS



Elevation. 1422 RB

Production. 5 BO / 175 BW

Figures indicate Bottom of Formations. 24 hr. State Productivity

CASING:
8 5/8" 219' cem.
5 1/2" 2831' cem.

shale, sand, shells, lime 219
shale, lime 320
lime, shale, sand 505
sand 581
shale 1145
shale, shells 1445
lime, shale 1840
sand, shale 1905
shale, shells 2030
lime 2290
lime, shale streaks 2380
lime, shale 2530
shale 2370
lime Miss., chert 2649
lime, shale 2808
lime RTD 2834
Total Depth

Tops:	Sample	Schlumberger
Conglomerate	-	2564
Mississippi	2569	2568
Kladerhook	2692	2692
Hanton	2827	2830
RTD	2832	2834

DST #1 2790-2821, Open 1 hr. SI 20 min.
Weak blow for 3 min. Rec. 5'
mud. IFP 0#, FFP 0#, BHP 0#.

DST #2 2826-32 Open 1 hr. SI 20 min.
Fair blow throughout. Rec. 50'
free oil & 55' HOCM, no water
BHP 950#, IFP 0#, FFP 50#.

Drilled cement & CO to RTD 2834.
1 hr., filled up 65';
2 hrs, " " 100'
Swbd 10 BF in 3 hrs., off bottom
(15% water.)
Az. w/250 gal. Swbd off load in
2 1/2 hrs. Swbd 55 BF, in 9 hrs.
P/5.6 BO / 40.6 BW/11 hrs.