

19-21-3E


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORPORATION
Farm- Slocombe No. 6

SEC. 19 T. 21 R. 3E
SW SW NE

Total Depth. 2913' Sch. T. D. 2912' RTD
Comm. 2-21-57 Comp. 3-1-57
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 5-4-57

County Marion KANSAS



Elevation. 1434' RB

CASING:

8 5/8" @123' cem.
5 1/2" @2893' cem.

Production. State Test Indicated
Capacity 2,879 BOPD & 5% wtr

Figures indicate Bottom of Formations.

sand & clay	123
lime	630
shale	1130
shale & lime	1795
sand	1900
shale & lime	2055
lime	2565
lime & chert	2660
lime & shale	2780
shale	2860
lime	2912 RTD
lime	2913 Sch. TD
Total Depth	

TOPS	SAMPLE	SCHLUMBERGER
Lansing	1998	2000
Conglomerate	2571	2570
Mississippi	2586	2587
Kinderhook	2676	2677
Hunton	2816	2816
Maquoketa	2856	2856
Viola	2883	2886

Perforation
Perf. 2816-26 w/4 sh ch per ft.
Filled up 1160' oil, no wtr, in 30 min.
" " 2600' " " " " 80 min.
Swbd 10' BPH for 17 hrs.
Bailed 1 1/2 bbls muddy water off bottom
POP