

19-21-3e

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANDERSON PRICHARD OIL CORPORATION
Farm- Slocombe No. 2

SEC. 19 T. 21 R. 3E
SE NW NE

Total Depth. 2861'

Comm. 8-14-56


Shot or Treated.

Contractor. Glenn W. Peel

Issued. 9-29-56

Comp. 8-21-56

County Marion KANSAS



Elevation. 1454' RB

Production. 208 BOPD & 4% wtr.

CASING:

8 5/8" @112' cem
5 1/2" @2859' cem.

Figures indicate Bottom of Formations.

surface soil	112
lime	280
lime & shale	510
lime	690
shale & lime	1060
shale	1365
lime & shale	1735
Lime & sand	1960
lime	2625
lime & chert	2710
lime & shale	2815
lime	2861

Total Depth

TOPS:

Conglomerate	2607
Mississippi Chat	2624
Kinderhook	2711
Hunton	2856

DRILL STEM TEST:

DST #1 2854-61. op. 30 ,in. SI 20 min.
Weak to no blow. Rec. 17' mud.
Pressures--zero

Drilled cem. & CO to 2861

Filled up 2200' in 30 min. (oil)

Filled up 2600' in 1 hr. (oil)

POP